

LEVEL *IV*

TECHNICAL REPORT HL-79-21



(12)

# MODIFICATIONS TO FILLING AND EMPTYING SYSTEM OF LOCK NO. 1, MISSISSIPPI RIVER MINNEAPOLIS, MINNESOTA

Hydraulic Model Investigation

by

Jackson H. Ables, Jr.

Hydraulics Laboratory


U. S. Army Engineer Waterways Experiment Station  
P. O. Box 631, Vicksburg, Miss. 39180

December 1979

Final Report

Approved For Public Release; Distribution Unlimited

DTIC  
ELECTE  
APR 24 1988  
C



Prepared for U. S. Army Engineer District, St. Paul  
St. Paul, Minnesota 55101

DDC FILE COPY

THIS DOCUMENT IS BEST QUALITY PRACTICABLE.  
THE COPY FURNISHED TO DDC CONTAINED A  
SIGNIFICANT NUMBER OF PAGES WHICH DO NOT  
PRODUCE LEGIBLY.

80 4 23 098

Destroy this report when no longer needed. Do not return  
it to the originator.

The findings in this report are not to be construed as an official  
Department of the Army position unless so designated  
by other authorized documents.

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER Technical Report HL-79-21	2. GOVT ACCESSION NO. AD-A083327	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) MODIFICATIONS TO FILLING AND EMPTYING SYSTEM OF LOCK NO. 1, MISSISSIPPI RIVER, MINNEAPOLIS, MINNESOTA; Hydraulic Model Investigation	5. TYPE OF REPORT & PERIOD COVERED Final report	
7. AUTHOR(s) Jackson H. Ables, Jr	6. PERFORMING ORG. REPORT NUMBER Jul 76-Feb 78	
9. PERFORMING ORGANIZATION NAME AND ADDRESS U. S. Army Engineer Waterways Experiment Station Hydraulics Laboratory P. O. Box 631, Vicksburg, Miss. 39180	8. CONTRACT OR GRANT NUMBER(s)	
11. CONTROLLING OFFICE NAME AND ADDRESS U. S. Army Engineer District, St. Paul 1135 USPO & Custom House St. Paul, Minn. 55101	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) 12156	12. REPORT DATE December 1979	
	13. NUMBER OF PAGES 120	
	15. SECURITY CLASS. (of this report) Unclassified	
	15a. DECLASSIFICATION/DOWNGRADING SCHEDULE	
16. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Hydraulic models Lock and Dam No. 1, Mississippi River Lock filling and emptying systems Locks (Waterways) Mississippi River		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The existing locks at Locks and Dam No. 1 were constructed between 1929 and 1932. Problems have been experienced with accumulation of ice and debris at the intakes, air entrapment in the culverts of the filling and emptying system, excessive turbulence in the lock chamber during filling, and hazardous conditions downstream from the locks during emptying operations. Also, the stoney gates used for control of filling and emptying, the miter gates, and miter gate operating machinery are in bad condition.		

(Continued)

DD FORM 1 JAN 73 1473 EDITION OF 1 NOV 65 IS OBSOLETE

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

414389

*[Handwritten signature]*



Unclassified

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

20. ABSTRACT (Continued).

> Various elements of the filling and emptying system were developed in a 1:25-scale hydraulic model for use in rehabilitating the locks. Both the landward and riverward locks were investigated and recommended design and modifications were furnished to accomplish rehabilitation of both locks although only the landward lock will be completely rehabilitated. Major modifications to the locks will include constructing new intake manifolds, lowering the roof of the filling and emptying culverts and changing their shape, constructing new sidewall ports, replacing the stoney gates with tainter valves, and constructing new culvert outlets.

With the rehabilitated system, the lock could be filled in 10.2 min and emptied in 10.6 min with a 4-min valve time and a 37.8-ft lift.

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

## PREFACE

The model investigation reported herein was authorized by the Office, Chief of Engineers, U. S. Army (OCE), on 23 June 1975 at the request of the U. S. Army Engineer District, St. Paul (NCS).

The study was conducted in the Hydraulics Laboratory of the U. S. Army Engineer Waterways Experiment Station (WES) during the period of July 1976 to February 1978 under the general supervision of Messrs. H. B. Simmons, Chief of the Hydraulics Laboratory, and J. L. Grace, Jr., Chief of the Hydraulic Structures Division, and under the direct supervision of Mr. G. A. Pickering, Chief of the Locks and Conduits Branch. The engineer in immediate charge of the model was Mr. J. H. Ables, Jr., assisted by Messrs. J. V. Hines, D. B. Murray, and C. L. Dent. This report was prepared by Mr. Ables.

During the course of this study, Messrs. S. P. Powell, Bruce McCartney, and H. Keith Snyder of OCE; J. F. Ordenez of the North Central Division; R. B. Fletcher, Joe Schultz, Grant Westall, Stuart V. Dobberpuhl, Chuck Spitzack, Alfred H. Mathews, John Plump, Stan Kumpula, Glen S. Bengtson, and Richard Pomerleau of NCS, and representatives of the Harza Engineering Co. visited WES to discuss test results and correlate these results with design work being accomplished concurrently.

Directors of WES during the conduct of the studies and the preparation and publication of this report were COL G. H. Hilt, CE, COL John L. Cannon, CE, and COL Nelson P. Conover, CE. Technical Director was Mr. F. R. Brown.

Approved For	
Reviewed	
Dissemination	
Classification	
Indexing	
Abstracting	
Publication	
Other	
Remarks	
A 73 yH	

## CONTENTS

	<u>Page</u>
PREFACE . . . . .	1
CONVERSION FACTORS, U. S. CUSTOMARY TO METRIC (SI)	
UNITS OF MEASUREMENT . . . . .	3
PART I: INTRODUCTION . . . . .	5
Present Situation . . . . .	5
General Description and History of Prototype Structures . . . . .	5
River Characteristics . . . . .	7
Major Hydraulic Problems at Existing Locks . . . . .	8
Purpose of Model Investigation . . . . .	10
PART II: THE MODEL . . . . .	11
Description . . . . .	11
Appurtenances and Instrumentation . . . . .	11
Scale Relations . . . . .	16
PART III: TESTS AND RESULTS . . . . .	17
Test Procedure . . . . .	17
Landward Lock Filling and Emptying System . . . . .	17
Riverward Lock Filling and Emptying System . . . . .	30
1:10-Scale Model Slide Gate Tests . . . . .	36
PART IV: DISCUSSION AND RECOMMENDATIONS . . . . .	40
TABLES 1-16	
PHOTOGRAPHS 1-7	
PLATES 1-62	

CONVERSION FACTORS, U. S. CUSTOMARY TO METRIC (SI)  
UNITS OF MEASUREMENT

U. S. customary units of measurement used in this report can be converted to metric (SI) units as follows:

<u>Multiply</u>	<u>By</u>	<u>To Obtain</u>
cubic feet per second	0.02831685	cubic metres per second
feet	0.3048	metres
feet per second	0.3048	metres per second
feet per second per second	0.3048	metres per second per second
inches	25.4	millimetres
miles (l. S. statute)	1.609344	kilometres
pounds (mass)	0.4535924	kilograms
square feet	0.09290304	square metres
tons (force)	8896.444	newtons
tons (2000 lb, mass)	907.185	kilograms




Figure 1. Locks and Dam No. 1

MODIFICATIONS TO FILLING AND EMPTYING SYSTEM OF LOCK NO. 1

MISSISSIPPI RIVER, MINNEAPOLIS, MINNESOTA

Hydraulic Model Investigation

PART I: INTRODUCTION

Present Situation

1. Locks and Dam No. 1 is located at Mississippi River mile 847.6 above the mouth of the Ohio River between the cities of St. Paul and Minneapolis, Minnesota (Figure 1). The project has been included in the Lock and Dam Replacement Program for a number of years. Early reports considered replacement of the entire lock and dam structure. In the interim period, several rehabilitation contracts have restored various components of this structure. Alternatives for rehabilitation of the lock filling and emptying system are now being investigated.\* Rehabilitation is defined as any work necessary to extend the life of the structure 40 years without increasing the depth, width, or length of the locks.

General Description and History of Prototype Structures

2. The original structure was completed and placed in operation in 1917 and included a 152-ft-long\*\* hydroplant adjacent to the left bank, a 574-ft-long dam surmounted by 2-ft-high automatic release flashboards and eight sluiceways (of which only three sluice gates are operated and maintained at the present time), and an 80- by 360-ft navigation lock. In 1929 the lock failed, cutting off all barge traffic to

---

\* U. S. Army Engineer District, St. Paul, "Study of Alternatives for Rehabilitation of Lock and Dam No. 1, Mississippi River, Minneapolis, Minnesota," Vols I and II, Apr 1976, St. Paul, Minn.

\*\* A table of factors for converting U. S. customary units of measurement to metric (SI) units is presented on page 3.

Minneapolis. To ensure against a future interruption to barge traffic, it was decided to build twin 56- by 400-ft locks at this site. The first lock (riverward lock) was completed in 1930 and the second lock (landward lock) was placed in operation in 1932. A plan and sections of the lock structures are shown in Plates 1-6.

#### Dam

3. The dam is a concrete structure and for the greater part is supported on an alluvial fill consisting primarily of sand, gravel, and limestone slabs; a portion of the dam and apron, however, is supported on timber piling. Along the upstream face of the dam is a steel-sheet piling cutoff wall; there is also a row of steel sheet piling along the toe of the apron as a preventive measure against scour. The crest and the downstream face have been resurfaced (1949-1953). A major portion of the apron has been replaced and a baffle wall was constructed on the apron to induce a hydraulic jump to overcome serious scour below the dam; this work was completed in 1953. In 1952 the dam was stabilized by placing sand fill in the interior to reduce the possibility of failure by sliding. Three of the eight sluice gates in the dam were rehabilitated and hydraulic machinery to operate them was installed in 1954. Under present pool conditions, the dam maintains a normal head of about 38.0 ft during the navigation season and about 36.0 ft during the winter season. In general, the dam is in good condition.

#### Riverward lock

4. The present riverward lock was built in 1929 and 1930 to replace the original lock which failed on 19 August 1929. The plan was to provide a structure suitable for 9-ft draft navigation based on the design pool level for Lock and Dam No. 2 which was then under construction. However, due to probable seepage damages, local interests obtained a court order limiting the elevation to which the pool could be raised to 685.7.\* Later, in 1934, the court approved the raising of the pool to el 687.2, 1.9 ft less than its designed height. As a result,

---

\* All elevations (el) cited herein are in feet referred to mean sea level (msl).

there is a depth of only 7.5 ft over the lower sill at flat pool (zero flow) or about 8.0 ft at normal tailwater elevation; hence, the lock has had little use except for an occasional locking of pleasure boats, empty barges, or shallow-draft towboats. The stability of the lock walls, the poor condition of the operating machinery, and the lack of guide walls which makes approaches difficult have also been factors in limiting the use of the riverward lock. Actually in building the riverward lock, the landward wall thereof was constructed of adequate width with two emptying and filling tunnels to serve as the intermediate wall of the twin locks when the second lock was constructed.

#### Landward lock

5. The present landward lock was built in 1931-1932 as a safeguard to maintain river traffic to and from Minneapolis. As a result of the failure of the original lock, Minneapolis was without barge line service for over a year; and it was determined that a recurrence should be avoided if at all possible. The downstream sill of this lock has a top elevation of 677.2 providing a depth of flat lower pool of 10.0 ft or about 10.8 ft at normal tailwater elevation; hence, the landward lock handles practically all traffic through this facility.

#### Hydroelectric plant

6. The hydroelectric plant, located at the east end of the dam, and flashboards on the crest of the dam are maintained by the Ford Motor Company.

### River Characteristics

7. Lower pool elevation at the site is controlled by Dam No. 2 near Hastings, Minn., and it is also influenced by discharges from the Minnesota River. During the period of 1951-1972, the average tailwater elevation was about 690.0 and the minimum elevation was as low as 586.2. The highest water level downstream of the dam was recorded at 719.0 on 17 April 1965.

8. Upper pool elevation at the site is controlled by the overflow dam and by discharges through the low-level sluices and through the Ford



power plant. During the navigation season, when flashboards on top of the dam are at a raised position, the headwater is kept normally at 725.0. The flashboards on the dam contain shear pins which fail due to ice pressure or high spring flows. During the winter months the water surface in the upper pool will thus be lowered to approximately el 723.0. The highest headwater elevation ever recorded, 734.5, occurred on 17 April 1965.

#### Major Hydraulic Problems at Existing Locks

9. Four major hydraulic problems exist at Locks and Dam No. 1:
  - a. Debris at intakes. The intake manifolds for the locks (Plates 2, 5, and 6) are located in the miter gate recesses. During filling, vortices form over the intakes and attract ice and floating debris into the gate recesses. This obstructs complete opening of the miter gates until the debris is removed. Lockages are delayed and under some conditions normal removal of debris can be hazardous.
  - b. Air entrapment. The crown of the 9.5-ft-diam filling and emptying culverts is at el 690.7 (Plates 3 and 4), 3.5 ft above normal lower pool elevation 687.2. Prior to filling, a layer of air is therefore resident in the level portion of the culverts and also in the sloping portions downstream of the filling valves (Plates 5 and 6). When the filling valves are opened, the intruding water compresses the air in the culverts and causes pulsating pressures on the downstream valves. Damage occurs to the roller train rollers and guide plates. Loud noises can be heard and vibrations of the lock walls can be felt. Air also enters the culverts through the upper bulkhead slots immediately downstream of the filling valves. There is a venting system in current use, but it is inadequate.
  - c. Lock chamber turbulence. When the lock chamber is being filled, jets issuing from the adjacent culvert-filling ports flow directly across the lock chamber and meet, causing excessive turbulence. This undesirable condition is further intensified by the size of the 10 ports (3 ft wide by 4 ft high) that are spaced 26 ft on centers in each wall. This results in an undesirable culvert-to-port-area ratio of 1:1.69. The insufficient submergence of the ports (2 ft above the port roof) permits entrapment and entrainment of air in the culvert which when passed into the lock chamber creates a highly turbulent condition.

Some air and entrained water is expelled through the vents. Manipulation of the culvert valves by the lock-master to lessen turbulence and reduce hawser forces on barge tows significantly increases lock filling time. When pleasure craft or small boats are locked, they must be moored near the miter gate sill where turbulence is less hazardous.

- d. Downstream conditions. During emptying operations, the discharge from the culverts in the intermediate wall flows directly into the approach channel (Plate 2). This discharge is not dissipated and generates large waves; consequently, small boats must remain more than 400 ft downstream to avoid being swamped. The landward culvert discharges through a manifold immediately downstream of the miter gate, and discharge from the river-wall culvert is turned 90 deg and directed toward a nearby island. These flows could endanger people or pleasure craft located in the area.

1C. The various hydraulic problems associated with the existing locks, as discussed in paragraph 9, were studied under contract by Mr. M. E. Nelson (NCS consultant). Results of his study, including a description of the problems and proposed solutions and modifications to the existing filling and emptying system to improve its operation and to reduce hazards to navigation, were presented in a report entitled "Hydraulic Problems and Recommended Solutions at Locks and Dam No. 1, Mississippi River." These recommendations were reviewed, and with suggestions by engineers of OCE, NCD, NCS, and WES,\* the elements of the existing lock systems to be modified are as follows:

- a. Construct new intake manifolds (Plate 7) upstream of the miter gate recesses to reduce the tendency for floating debris to interfere with opening of the miter gates. The intake should remove vortex problems and improve efficiency of the filling system.
- b. Relocate the filling valves to the lower culvert level with invert el 681.2 (later changed to el 678.7). Air entrainment and surges will be reduced by this modification (Plates 8 and 9).
- c. Replace the present stoney filling and emptying valves

---

\* OCE, Office, Chief of Engineers; NCD, U. S. Army Engineer Division, North Central; NCS, U. S. Army Engineer District, St. Paul; and WES, U. S. Army Engineer Waterways Experiment Station.

with new reverse tainter valves (Plates 8 and 9), vertical-lift gates, or butterfly valves.

- d. Lower the existing 9.5-ft-diam culverts at invert el 681.2 to invert el 678.7 and change to 9.5-ft-wide by 7.5-ft-high rectangular culverts, in order to exclude or reduce air in the culvert crowns at normal tailwater el 687.2 (Plates 9 and 10).
- e. Lower the ports in the lock walls to discharge flush with the lock chamber floor and increase submergence of the jets emerging from the ports during the filling cycle. Design the ports for a more optimum culvert-to-port-area ratio and stagger the ports in opposing lock walls (Plates 8 and 9).
- f. Consider elimination of the existing venting system by improvements suggested above (subparagraphs a-d).
- g. Provide energy dissipation in the lower lock approach by constructing bottom interlaced laterals downstream of each lock chamber (Plates 10 and 11). Consider alternate proposals for discharges from the river-wall culvert (Plate 12).

#### Purpose of Model Investigation

11. It was recognized that the improvements to the hydraulic filling and emptying system listed in paragraph 10 constituted significant departures from the existing design. Since assurance was necessary that the proposed structurally feasible modifications would result in the acceptable performance they were intended to provide, a model study of the modified system was required to confirm the hydraulic adequacy of the modified filling and emptying system.

## PART II: THE MODEL

### Description

12. The 1:25-scale lock model reproduced approximately 600 ft of the upstream approach, the entire landward filling and emptying system including intakes, culvert tainter valves in longitudinal wall culverts, the interlaced outlet, and about 500 ft of downstream approach (Figures 2-7 and Plate 13). The riverward lock intake and outlets were blocked out to permit initial tests of the landward lock modifications. Upon completion of the landward lock modification tests, the downstream topography and emptying system for the riverward lock were installed and the modifications for the riverward lock were developed. The lock approach topography was molded in concrete. The lock chamber was constructed of plywood and the intakes, longitudinal wall culverts, and sidewall port manifolds and outlets were reproduced in plastic. The culvert valves were constructed of sheet metal and fitted with rubber seals to prevent leakage. Six sheet-metal barges, each simulating a length of 120 ft and a width of 25 ft (Plate 14), were loaded with weights to reproduce the desired drafts of 9.0 ft on the landward lock and 6.5 ft on the riverward lock.

### Appurtenances and Instrumentation

13. Water was supplied to the model through a circulating system. Both the headbay and tailbay of the model contained skimming weirs that maintained essentially constant upper and lower pools during filling and emptying operations. Vertical adjustments of the skimming weirs permitted simulation of any desired upper and lower pool elevations. Dye and confetti were used to study surface and subsurface current directions. Pressure cells were used to measure instantaneous pressures at selected locations in the culvert system.

14. The instrumentation and control system provided for operation of the culvert reverse tainter valves and later slide valves (Figures 3




Figure 2. General view of model looking downstream




Figure 3. Close-up of  
landwall lock intake  
manifold, miter gates,  
and culvert valve drive  
equipment

Figure 4. Valve drive equipment




Figure 5. Chamber and sidewall  
port manifold



Figure 6. Close-up of outlet for landwall lock




Figure 7. Outlet and lower approach for landwall lock

and 4) were simulated by means of a programmable d-c motor. The position of the valve opening was indicated by a linear potentiometer. The command signal plot was drawn to carefully control the valve position as a function of time. The control system was further enhanced by introducing two electromagnetic clutches to provide for both normal (dual) and single culvert valve control. The lock water surface was monitored by means of a commercial water level probe.

15. A hawser-pull (force links) device used for measuring the longitudinal and transverse forces acting on the upstream and downstream ends of a tow in the lock chamber during filling and emptying operations is shown in Figure 8. These links were machined from aluminum and had SR-4 strain gages cemented to the inner and outer edges. When the device was mounted on the tow, one end of the link was pin-connected to the tow while the other end engaged a fixed vertical rod and was free to move up and down with changes in the water-surface elevation in the locks. Any horizontal motion of the tow caused the links to deform and



Figure 8. Hawser force links



vary the signal to a recorder. The links were calibrated by inducing deflection with known weights.

16. Data were recorded graphically on a commercial recorder. The sensing elements (mechanical-to-electrical conversion devices) located at various points on the model were connected by shielded cables to amplifiers where the outputs were stepped up to the level required for graphical recording.

### Scale Relations

17. The accepted equations of hydraulic similitude, based upon the Froudian relations, were used to express the mathematical relations between the dimensions and hydraulic quantities of the model and the prototype. General relations for transference of model data to prototype equivalents are presented in the following tabulation.

<u>Dimension</u>	<u>Ratio</u>	<u>Model Scale Relations</u>	
		<u>Lock</u>	<u>Gate</u>
Length	$L_r = L$	1:25	1:10
Area	$A_r = L_r^2$	1:625	1:100
Velocity	$V_r = L_r^{1/2}$	1:5	1:3.162
Time	$T_r = L_r^{1/2}$	1:5	1:3.162
Discharge	$Q_r = L_r^{5/2}$	1:3,125	1:316.23
Weight	$W_r = L_r^3$	1:15,625	1:1,000
Force	$F_r = L_r^3$	1:15,625	1:1,000

### PART III: TESTS AND RESULTS

#### Test Procedure

18. Evaluation of the various elements of the filling and emptying systems shown in Table 1 was based on data obtained during general filling and emptying operations with a 37.8-ft head differential (upper pool el 725.0 and lower pool el 687.2) and submergences of 11 ft in the landward lock and 8.5 ft in the riverward locks, which had chamber invert elevations of 676.2 and 678.7, respectively. Performance was primarily based on flow conditions and distribution at the intakes, at the outlets, and in approaches to the lock; turbulence and hawser forces measured on tows moored in the lock chamber; pressure measurements throughout the system and particularly below the filling and emptying culvert valves and/or slide gates; and filling and emptying times. In determination of flow distribution in portions of the system, and in some studies of approach and exit conditions, fixed heads and steady-flow conditions were maintained with the culvert valves and/or miter gates fully or partially open. For steady-flow tests, water-surface elevations within the lock chamber were set in accordance with conditions expected at a given instant of time from filling and emptying curves recorded for particular valve or slide gate opening schedules.

#### Landward Lock Filling and Emptying System

##### Type 1 (original) system

19. The type 1 design filling and emptying system shown in Plates 15-17 was designed to utilize as much of the existing culvert and culvert alignments as possible with the lock chamber and sills unchanged. Modifications were made to the intermediate wall nose, intakes, culverts, sidewall port manifold, interlaced lateral outlets, and filling and emptying valves. The shape of the culvert was changed from round to rectangular and the invert was lowered as much as existing structural and foundation considerations would permit. Primary elements of the

system consisted of six-port, sidewall intake manifolds entering 8-ft-wide by 10-ft-high culverts in each wall at invert el 708.7. The culvert then dropped 30 ft to el 678.7 while transitioning to an 8-ft-wide by 7.5-ft-high section at the reverse-mounted culvert tainter valves. From the valves, the culvert transitioned to a 9.5-ft-wide by 7.5-ft-high section for the sidewall port manifold that consisted of 19 ports in each culvert, spaced 13 ft on centers and staggered in each wall, with individual port throats 1.5 ft wide by 2.3 ft high. This resulted in a culvert-to-port-area ratio of 0.92. An 8-ft-wide by 7.5-ft-high transition connected the chamber manifold to reverse tainter emptying valves, and the culverts emptied through three interlaced lateral outlets from the two wall culverts downstream of the lower miter gates.

20. Upstream approach and type 1 intake manifold. During preliminary observations the 5-ft radius installed on the intermediate wall nose intake (Plate 15) was found to be too short and inadequate as swirls, vortices, and an air-entraining vortex formed at port 1. The 5-ft radius was increased to 12.5 ft which extended the nose 7.5 ft farther upstream to sta 0+96 (type 2 nose, Plate 18). Surface current patterns in the upstream approach area and in the intermediate vicinity of the type 1 intakes with the type 2 intermediate wall nose were recorded by means of 5-sec-sequence (exposure) Photos 1a-1f during a typical 4-min valve filling operation. The culvert valve operating schedule is shown in Plate 19. These photographs were recorded prior to and at 2, 4, 6, 8, and 10 min after the start of a 4-min valve filling operation. The surface currents at 8 and 10 min have reversed with movement away from the intakes and toward the river approach. Swirls will occur in the prototype, but vortex or air-entraining vortex problems will not result. Similar observations with the upper pool lowered 2 ft to el 723.0 resulted in no perceptible difference in surface currents as they appeared in Photos 1a-1f. During the navigation season, the headwater is kept normally at el 725.0. The flashboards on the dam contain shear pins which fail due to ice pressures or high spring flows. During the winter months the water surface in the upper pool will thus

be lowered to approximately el 723.0. Submergence\* over the intake roof at el 713.7 is 11.3 ft with normal upper pool 725.0, and 9.5 ft with upper pool at el 723.0.

21. Velocities at the wall face of the type 1 intake ports were measured under steady-flow conditions, and these velocities and resulting flow distribution are plotted in Plate 20. Flow was divided with 50.9 percent through the intermediate wall intake and 49.1 percent through the land wall intake, and distribution across the manifold was considered to be satisfactory. Steady-flow pressures in and throughout the filling system are shown in Table 2. Piezometer locations are indicated in Plate 21. The type 1 intake and type 2 intermediate wall nose in Plates 15 and 18 were recommended for inclusion in the landward lock rehabilitation.

22. Pressures at the filling and emptying culvert valves. Sub-atmospheric pressures were observed with pressure cells installed on the roof of the culvert (el 686.2) downstream of the filling and emptying valves at sta 0+95.45 and 4+21.87B (Plates 21 and 22). The bulkhead slots upstream and downstream of the filling valves were sealed at the roof of the culvert during these measurements to prevent the drawing of large amounts of air into the filling system unnecessarily. Relief of the subatmospheric pressure conditions by means of controlled air venting will be discussed later. The bulkhead slots upstream and downstream of the emptying valves were not sealed and controlled air venting will also be needed to relieve low pressure conditions.

23. Turbulence in the lock chamber and hawser forces on tows moored in the chamber with type 1 sidewall port manifold. During filling operations turbulence in the lock chamber was considered to be excessive with the type 1 system. The sidewall port manifold with sloping ports (Plate 16) 7.25 ft long on the land wall and 5.08 ft long on the intermediate wall directed the jets downward, from the culvert invert at el 678.7 to the chamber invert 2.5 ft lower at el 676.2, in

---

\* Submergence is the difference in elevation between the lower pool and the lock chamber floor.

such a manner that flow spread hand-fan-shaped fashion and the opposing jets met near the center of the lock chamber and rolled back toward the lock walls. Figure 9 shows this type of action, flow from manifold ports 10 to 3 1 min after beginning of a 4-min valve filling operation. Sequence Photos 2a-2f show confetti movement (5-sec exposure) on the lock chamber water surface during a similar filling operation. Foundation problems in the existing lock necessitated the 2.5-ft difference in culvert and chamber invert elevations. This required sloping of the ports negated to some degree the optimum design of the manifold with respect to culvert and port throat-area ratio and port spacing and staggering in opposite walls.

24. Hawser forces were measured during filling and emptying with a 6-barge tow at 9-ft draft (4,844-ton displacement) with the upstream end of the tow at sta 0+65 B. Hawser forces versus lock filling and emptying times are shown in Plate 23. Similar data for the same head




Figure 9. Path of jets from intermediate wall after beginning of filling operation, type 1 (original) design

differential and 2 ft higher upper and lower pools are also indicated in Plate 23. Although hawser forces did not exceed the 5-ton criterion for barge tows, turbulence described in paragraph 23 was most unsatisfactory, particularly for small craft; and it was obvious that further development of the sidewall port manifold would be necessary.

25. Type 1 outlets and lower approach. Details of the type 1 outlets and lower approach are shown in Plates 10 and 17 and Figures 6 and 7. Velocities recorded at the face of the outlet lateral ports and the resulting flow distribution under steady-flow conditions are plotted in Plate 24. Flow was divided with 49.6 percent through the land wall laterals and 50.4 percent through the intermediate wall laterals. Steady-flow pressures observed in the emptying system are shown in Table 3. Piezometer locations are shown in Plate 21. Figure 10 shows flow conditions at the outlet with maximum discharge for a normal head and 4-min valve time. Velocities and flow distribution at the type 1 outlets and flow conditions in the lower approach were satisfactory. These outlets are recommended for use in rehabilitation of the landward lock.

26. Overall lock coefficients. The culvert valve schedule in Plate 19 for valve times of 2, 4, 6, and 8 min resulted in filling and emptying times shown in Plate 25. Overall lock coefficients ( $C_L$ ), based on these data, were computed by the equation

$$C_L = \frac{2A_L (\sqrt{H+d} - \sqrt{d})}{A_c (T - Kt_v) \sqrt{2g}}$$

where

$A_L$  = area of lock chamber, sq ft

$H$  = initial head, ft

$d$  = measured overfill or undertravel, ft

$A_c$  = area of culvert, sq ft

$T$  = filling or emptying time, sec

$K$  = a constant

$t_v$  = valve time, sec

$g$  = acceleration due to gravity,  $\text{ft/sec}^2$




Figure 10. Flow conditions during peak discharge at type 1 (original) design outlet, 4-min valve time

The term  $T - Kt_v$  is lock filling or emptying time for the hypothetical case of instantaneous valve opening as is obtained directly from the curves plotted in Plate 25. Computed overall lock coefficients for the type 1 (original) system were 0.59 for filling and 0.57 for emptying.

#### Alternate systems

27. The original sidewall port manifold required additional modification and testing. For optimum performance the wall culverts, ports, and lock chamber would have a common invert el 671.7, which is 15.5 ft below lower pool el 687.2. This would provide 6.5-ft clearance for dissipation of port jet energy beneath a 9-ft draft tow. Due to foundation and structural problems, instead of 15.5-ft submergence over the lock floor there was a minimum submergence of only 11 ft and 2-ft

clearance beneath a 9-ft draft tow. Also, because of foundation and structural problems, the ports were sloped downward 2.5 ft from the invert of the culvert to the chamber invert. Thus, the jets were forced into the invert and dissipated in the hand-fan-shaped fashion in this area, reflected upward toward the center line of the chamber, and rolled back toward the wall from which flow entered, which generated subsurface and surface turbulence in the lock chamber. Tests were conducted with various deflector walls and trenches in an effort to reduce the high degree of turbulence observed with the type 1 system. Tests were also conducted with the wall culvert, port, and chamber floor at a common invert elevation to determine what effect this would have on turbulence and hawser forces. All of the sidewall port modifications were tested with other elements of the systems unchanged from the type 1 system.

28. Type 2 sidewall port manifold and system. Port deflectors 1 to 2 ft high and 3 ft long (Plate 26) were tested in an effort to reduce the spreading of the sloping port jets and turbulence in the chamber. The type 4 deflector (4 ft long and 1 ft high) was the most satisfactory and was selected as an element of the type 2 sidewall port manifold and system. Figure 11 shows the path of the jets issuing from the intermediate wall ports 10 to 3 1 min after beginning of a 4-min valve opening. A considerable reduction in jet spread and control of flow across the lock is apparent when the type 1 manifold jets in Figure 9 are compared with the type 2 manifold jets in Figure 11. Sequence photographs of confetti movement on the chamber water surface with a 4-min valve time are presented in Photos 3a-3f. The deflectors significantly improved turbulence in the chamber as can be seen by comparing Photos 2a-2f (type 1) with Photos 3a-3f (type 2). The type 4 deflectors in the type 2 system were 1 ft high and with only 1-ft minimum clearance between the deflector and a 9-ft draft tow, problems could be encountered during entering or exiting as well as during emptying operations due to squat\* of the towboat and tow, and undertravel at the end of emptying

---

\* Squat is the settling of a towboat or tow at a deeper draft in the available submergence in the lock chamber due to the increased power applied to move or slow a tow within the confines of a lock chamber.





Figure 11. Path of jets from intermediate wall after beginning of filling operation, type 2 sidewall port manifold design

operations. In the model tests, the 1-ft clearance between the top of the deflector and bottom of a 9-ft draft tow was adequate during emptying undertravel; however, the practicality of this small amount of clearance was considered marginal for tows entering and exiting the lock chamber.

29. Comparison of filling and emptying times for types 1 and 2 systems with normal and single (right) culvert operations are shown in Plate 25. Maximum longitudinal hawser force data on a 6-barge tow at 9-ft draft are compared in Plate 27.

30. Type 3 sidewall port manifold and system. Since the use of deflector walls in type 2 sidewall port manifold and system was not a feasible or practical solution to the control of jet flow from the sidewall port manifold, the manifold port jets were investigated with various lengths of 1- and 2-ft-deep trenches in the floor of the lock chamber immediately in front of each port (Plate 28). The 0.75-ft-radius

curves at the side of the portals adjacent to the chamber were removed so that the ports entered the chamber and trench at a 2.10-ft width on the land wall side and 1.88-ft width on the intermediate wall side. The invert slope of each port was extended past the chamber and port wall face into the trench at the invert depth being investigated. In addition to the types 1-8 trenches shown in Plate 28, performance was observed with sloped as well as square ends in the trenches. Turbulence in the lock chamber was less with the type 8 trench in front of the sidewall port manifolds. This trench was 1 ft deep at invert el 675.2 and 28 ft long to the center line of the lock chamber. The type 1 manifold modified to include the type 8 trenches was designated the type 3 manifold and system. The port jet tends to follow the trenches as shown in Figure 12, a photograph of the jets discharging from intermediate wall ports 10 to 3 (left to right or top to bottom of the figure) 1 min after the start of a 4-min valve opening. Sequence photographs of



Figure 12. Path of jets from intermediate wall after beginning of filling operation; type 3 sidewall port manifold design

confetti on the chamber water surface are presented in Photos 4a-4f. These photographs show that the turbulence was most satisfactory. The Photos 4a-4f sequence can be compared with similar Photos 2a-2f for type 1 and Photos 3a-3f for type 2 manifolds and systems.

31. Type 4 sidewall port manifold system. Since the riverward lock design had the wall culvert, ports, and chamber invert at a common invert elevation of 676.2, it was decided to make comparative tests of this system after the model was revised to simulate the riverward lock. This was accomplished by raising upper and lower pool elevations 2.5 ft and maintaining initial submergence of 11 ft in the chamber and a 37.8-ft head as in previous tests of types 1 to 3 manifolds and systems. The culvert roof was submerged 3.5 ft instead of 1 ft in tests of types 1 to 3 systems; this was designated the type 4 system (Table 1).

32. Observance of turbulence in the lock chamber during filling and emptying indicated good distribution of flow throughout the chamber. A photograph of the path of jets from the intermediate wall ports 10 to 3 (left to right or top to bottom of photograph) obtained 1 min after the 4-min valve began to open is shown in Figure 13. The dye jets and strings on the lock chamber floor indicate the existence of well-directed flow with a minimum of disturbance in the area when the flow from the staggered ports intermingled. There was sufficient rubbing of the jets and accompanying energy dissipation to prevent the jets from reaching the opposite wall with excessive energy of strength to induce adverse upwelling along the wall. Sequence photographs of confetti movements on the water surface during filling with a 4-min valve time are shown in Photos 5a-5f.

33. Maximum hawser forces versus filling and emptying times for 6- and 2-barge tows at 9-ft draft are plotted in Plate 29. Hawser forces did not exceed the 5-ton criterion for barge tows with valve times between 2 to 8 min. Similar data for single (right) culvert operations are plotted in Plate 30.

34. Minimum pressure gradient elevations (ft msl) versus filling and emptying times with normal and single (right) culvert operations are plotted in Plate 31. The shaded data were recorded with upper and lower



Figure 13. Path of jets from intermediate wall after beginning of filling operation; type 4 sidewall port manifold design. Chamber floor invert el 678.7, upper pool el 727.5, lower pool el 689.7, 11-ft submergence

pools raised 2.5 ft above normal (unshaded) conditions. The shaded data reflect 11-ft initial submergence over the chamber floor and 3.5-ft initial submergence over the roof of the culvert. The unshaded data are for 8.5-ft initial submergence over the chamber floor and 1.0-ft initial submergence over the roof of the culvert.

Recommended (type 3) systems

35. The type 3 (recommended) filling and emptying system (Table 1) for the landward lock site consisted of the following elements.

- a. Type 2 intermediate wall nose (Plate 18).
- b. Type 1 intake manifold (Plate 15).
- c. Culvert reverse tainter valves (Plates 9, 15, and 17). Subsequent test of slide gates in the 1:25-scale model for the riverward lock site and in a 1:10-scale model (for the purpose of studying hoist loads) indicated

satisfactory performance. However, the sponsor preferred the reverse-mounted culvert tainter valves due to the proven success with this type of valve experienced over long periods of lock operations at other Corps of Engineer navigation locks. It was recommended that vertically framed tainter valves developed during model tests of the Holt Lock\* for the U. S. Army Engineer District, Mobile, be adopted for Lock No. 1 modifications.

- d. Type 3 sidewall port manifold.
- e. Type 1 discharge outlets (Plate 17).

36. Comparisons of filling and emptying times for filling and emptying systems types 1-4 for normal and single valve operations are plotted in Plate 32. Maximum hawser forces measured on a 6-barge tow at 9-ft draft are plotted in Plate 33. These plots reveal very small differences in filling and emptying times and hawser forces. However, the water-surface turbulence was considered to be more satisfactory for types 3 and 4 systems (compare Photos 4a-4f and 5a-5f). The type 3 system appears to be the most feasible and economic because the type 4 system, as developed in model tests for the landward lock, requires lowering the culvert manifolds 2.5 ft from invert el 678.7 to el 676.2.

37. Average pressures throughout the type 3 system during filling and emptying operations are listed in Tables 4 and 5. Piezometer locations are shown in Plate 21. Subatmospheric pressures were recorded on the roof of the culvert downstream of the filling and emptying valves by means of pressure cells installed at sta 0+95.45B and 4+21.87B. Minimum pressure gradient elevations (ft msl) versus filling and emptying times for 2-, 4-, 6-, and 8-min valve times are plotted in Plate 34. The bulkhead slots upstream and downstream of the filling valves were sealed at the roof of the culvert. The bulkhead slots upstream and downstream of the emptying valves were not sealed. Similar data for single (right) culvert valve operations are plotted in Plate 34. Single 12-in.-diam air vents should be flush-mounted at all valves on the roof of the

---

\* T. E. Murphy and J. H. Ables, Jr., "Lock Filling and Emptying System, Holt Lock and Dam, Warrior River, Alabama; Hydraulic Model Investigation," Technical Report No. 2-698, Nov 1965, U. S. Army Engineer Waterways Experiment Station, CE, Vicksburg, Miss.

culvert about 3.5 ft (one-half the culvert height) downstream of the reverse tainter valve to prevent the potential for structural damage due to cavitation. Control valves (which can be locked after setting) should be installed on the air vents at the top of the lock wall to provide for a controlled admission of air in the prototype. At the time the modifications to the existing lock are placed in operation, hydraulic design personnel of NCS and WES should assist in determining the vent valve control settings that will preclude cavitation without an excessive amount of air and additional turbulence in the lock chamber. This has been done successfully at several locks and experience has shown that satisfactory performance can be obtained within a range of settings. The vent valves should then be locked at the desired position to prevent accidental changing of the setting. Additional information on design of culvert valve vents is given in paragraphs 2-5 of EM 1110-2-1610, 15 August 1975, "Hydraulic Design of Lock Culvert Valves."

38. Maximum hawser forces versus filling and emptying times measured with 6- and 2-barge tows at 9-ft drafts are plotted in Plate 35. Hawser forces did not exceed the 5-ton criterion for barge tows at valve times of 2, 4, 6, and 8 min. Similar data for single (right) culvert valve operations are shown in Plate 36. The high transverse hawser forces acting on the tow toward the right wall, which contains the filling culvert, are to be expected since the model tow was moored at the center line of the lock chamber and full force is allowed to develop in this direction. A tow moored at floating mooring bits in the right wall would rise vertically with the tow securely snubbed in position without any difficulty.

39. Delayed valve operations were considered prior to initiation of model testing and several delayed valve operations were investigated using the kinematics of a 4-min valve schedule and introducing a 2-min delay in opening at 1.5, 1.75, and 2.0 min, and then continuing until the valve reaches the fully open position in 6 min. Hawser forces and minimum pressures on the culvert roof downstream of the valves are plotted in Plate 37. Delayed valve operations require slightly longer to fill and empty with no significant advantages in hawser forces or

minimum pressures at the valves. In addition, prototype valve operating equipment would be more complicated.

40. The type 3 filling and emptying system should be operated with either a 4- or 2-min valve schedule as shown in Plate 19. Filling and emptying times are shown in Plate 32. Computed overall lock coefficients for the type 3 (recommended) system were 0.57 for filling and 0.54 for emptying.

#### Riverward Lock Filling and Emptying System

41. The riverward lock, as a result of existing conditions, has only 8.5 ft of submergence over the chamber floor and 1 ft of cover over the roof of the culverts. A normal head of 37.8 ft and normal upper and lower pools of 725.0 and 687.2, respectively, were reproduced in all riverward lock tests. Barge tow draft, because of the available 8.5-ft submergence, was limited to 6.5 ft in all riverward lock tests.

#### Type 4 system

42. Riverward lock tests were initiated with the recommended elements of the type 4 system for the landward lock, and the sidewall port manifold (Figure 14, Plate 38), culvert, ports, and chamber at invert el 678.7 (type 4, Table 1). Turbulence on the lock chamber water surface is indicated in sequence Photos 6a-6f. The degree of turbulence was considered to be satisfactory. Plots showing filling and emptying characteristics with a 6.5-ft-draft tow and pressures downstream of the reverse tainter valves are presented in Plates 30-32 and 39. A request was made by the sponsor to measure hawser forces on a single line of three barges aligned end to end, as well as on a full 6-barge tow for normal and single (right) culvert operations. These data are shown in Plates 40 and 41. The type 4 system, with only 8.5-ft minimum submergence over the lock floor, performed satisfactorily with tows loaded to 6.5-ft draft. Average pressures throughout the type 4 system with 4-min valve schedule are listed in Tables 6 and 7. Piezometer locations are shown in Plate 21. Filling culvert piezometers A-E were added on the invert of the right wall culvert drop section upstream of the filling




Figure 14. Sidewall port manifold prior to installation

valve, and piezometers C' and C'' also were added in the same vicinity on the roof of the culvert immediately downstream of the bulkhead at sta 0+37B. Average pressure conditions throughout the system were found to be satisfactory. Minimum culvert roof pressures downstream of the culvert valves are shown in Plate 31.

#### Type 5 system

43. The reverse tainter control valves installed in the wall culverts for all model tests of the types 1-4 systems were replaced with slide gates in the type 5 system. The slide gate and gate slot design are shown in Plates 42 and 43. The type 5 system is shown schematically with piezometer locations in Plate 44. The slide gates for filling operations were essentially in the same position as the lower lip of the tainter valves in this closed position. However, the emptying slide gates were located approximately 78 ft farther downstream than the tainter valves in order to possibly utilize the existing prototype



stoney valve slots. Except for the installation of slide gates, the type 5 system was identical with the type 4 system.

44. Plate 19 shows the proposed constant-speed gate schedule used in all slide gate operations. Filling and emptying times versus valve times are presented in Plate 45. Average pressures throughout the system with a 4-min valve time are listed in Tables 8 and 9. Minimum pressures recorded with pressure cells on the culvert roof immediately downstream of the slide gates during normal and single (right) culvert operations are plotted in Plate 46. Table 10 is a tabulation of visual observations of minimum water-surface levels in the bulkhead slots immediately upstream of the filling and emptying gates during 2-, 4-, 6-, and 8-min normal and single gate operations. During emptying operation, the bulkhead water level dropped to the culvert roof at el 686.2. Although no air entered the emptying culvert from the slot, the condition is marginal; and air could be expected to enter the culvert in the more efficient prototype structure. Thus, provisions to seal the bulkhead slots upstream as well as downstream of the emptying valve and downstream of the filling valve should be provided if the slide gates are adopted for modification of the riverward lock system.

45. Maximum hawser forces during filling and emptying operations with normal and single (right) gate operations were measured with 6- and 2-barge tows at 6.5-ft draft (Plates 47 and 48). The hawser forces were considered to be satisfactory. The comment regarding transverse hawser forces on single gate filling operation in paragraph 38 is pertinent to all sidewall port filling systems.

46. The type 5 system was more efficient than the systems with the reverse tainter valves. Normal filling and emptying operations required about 1 min less time, and there was a reduction of about 2 min during single culvert filling and emptying operations. The type 5 system (Table 1) performed satisfactorily in all respects for a system with a minimum of 8.5-ft submergence in the chamber at lower pool and barge tow draft limited to 6.5 ft.

#### Type 6 system

47. The filling system in the type 6 system was identical with

the type 5 system. Thus, no additional filling tests were conducted with this system. The type 6 emptying system (Table 1) included a three-lateral outlet positioned left of the intermediate wall culvert in the lower riverward lock approach for the right culvert (type 2 design, Plate 49) and a four-port outlet (type 3, Plate 12) for the left culvert. These outlets are shown in Figure 15. The riverward outlet discharged into a 45-ft-wide channel with invert elevation of 677.0, and this channel was positioned behind the high topography adjacent to the left guard wall downstream of the lock as shown in Plate 50. The dashed lines at the lower left end of the riverward outlet channel in Plate 50 indicate a transition from invert el 677.0 to existing topography to permit smooth outlet flow into the river. Both slide gates for the type 6 emptying system were moved 95.5 ft upstream, from sta 4+94B in the type 5 system to sta 3+98.50B in the type 6 system, as shown in Plate 49.




Figure 15. General view of lower approach to type 6 filling and emptying system with types 2 and 3 outlets for riverward lock installed

Photos 7a-7c show 4-min slide gate operations with peak discharge conditions for normal (Photo 7a), single (right, Photo 7b), and single (left, Photo 7c) culvert operations. There appeared to be no problem in the lower approach area during any of the operations. The turbulence in the lower approach was confined to the immediate vicinity above and adjacent to the laterals with slightly greater flow near the first ports in each lateral. This was not considered to be a problem since tows or small craft are not permitted in this area prior to completion of an emptying operation.

48. Velocities measured at the face of the types 2 and 3 outlets and the resulting flow distribution under steady-flow conditions are shown in Plates 51 and 52. The distribution of flow was 43.2 percent through the right outlet and 56.8 percent through the left outlet. In the right culvert outlet, laterals 1 and 2 each passed slightly more than a third of the right culvert total flow and lateral 3 carried slightly less than a third of the flow. In the riverward outlet, port 1 carried about 21 percent while ports 2-4 passed the balance of left culvert flow in near equal amounts. Flow in the outlets was considered to be satisfactory. Steady-flow pressures in the type 6 emptying system are listed in Table 11. Piezometer locations are shown in Plates 44 and 53. Average pressures throughout the type 6 emptying system with 4-min valve times are shown in Tables 12-14. Plate 54 is a plot of minimum pressures measured with a pressure cell mounted flush with the culvert roof 5 ft downstream of the emptying gate (Plate 53). The bulkhead slots downstream of the slide gates were sealed at the culvert roof. Table 15 is a record of visual observations of the water level in the bulkhead slots located 10 ft upstream of the slide gates during emptying operations. For all gate-operating schedules the water level reached the roof of the culvert. No air was admitted at the slot into the right (intermediate) culvert for normal or single gate operations; however, air was entrained through the slot into the left (riverward) culvert flow for some normal and single gate operations (Table 15). Since the prototype lock is expected to be about 10 percent more efficient than the 1:25-scale model, air can be expected to enter the prototype culvert

through the bulkhead slots 10 ft upstream of the slide gate. The air entrainment will occur after or near full gate opening and minimum pressures downstream of the slide gates will have already occurred. Therefore, provisions should be provided in the prototype to seal the bulkhead slots upstream and downstream of the slide gates near the culvert roof, and a controlled 12-in.-diam air vent should be positioned on the center line of the roof about 3.5 ft downstream of the slide gate. The controls should be located at the top of the lock wall to permit control adjustment and locking by representatives of NCS and WES prior to opening the lock system should the type 6 emptying system be adopted for modernization of the riverward lock at Lock No. 1.

49. Maximum hawser forces on 6- and 2-barge tows at 6.5-ft draft versus emptying times are plotted in Plate 55. Hawser forces did not exceed 3 tons. Plate 56 is a plot of emptying times versus slide gate times and these plots were used in computing overall lock coefficients of 0.59 for normal emptying, 0.52 for single (right) culvert emptying, and 0.61 for single (left) culvert emptying. The equation for these computations is shown in paragraph 26.

#### Recommendations

50. All of the filling and emptying systems tested for the riverward lock performed satisfactorily and any of these systems would be adequate for rehabilitating the existing lock. Little difference could be detected in the hydraulic performance of the lock when either tainter valves or slide gates were used to control filling and emptying. If tainter valves are used, they should be the vertically framed type referenced in paragraph 35. A 4-min opening schedule as shown in Plate 19 is recommended. Controlled air vents (12-in. diam) will be required at each valve as described in paragraph 37.

51. Either the type 1 interlaced lateral outlet (Plate 17) or the separated types 2 and 3 outlets (Plates 49 and 12) performed satisfactorily. The types 2 and 3 outlets were designed to remove a portion of emptying discharge away from the lower approach of the riverward lock, particularly since the landward lock empties in an adjacent area. However, under normal circumstances, it is very unlikely that the

lockmaster would allow simultaneous emptying operations of the locks, even if both locks were operable and active.

#### 1:10-Scale Model Slide Gate Tests

52. As a part of the preliminary design studies for Lock No. 1, the sponsor requested model tests to determine hoist loads on a proposed slide gate design (Plates 42 and 43), which was under consideration for control of the filling and emptying operations. Slide gates performed satisfactorily in 1:25-scale model tests of the types 5 and 6 filling and emptying systems as discussed in paragraphs 43-48. The alternate proposal of slide gates in lieu of tainter valves was under consideration because of relative estimated cost and related service factors. After completion of the 1:25-scale model test, a 1:10-scale model of the slide gate and a single culvert was constructed (Figures 16 and 17) to determine pressures near the gate and hoist loads on the gate. Figure 18 shows the model test gate which simulated a prototype gate with a dry weight of 4,209 lb and a submerged weight of 1,814 lb.

53. The slide gate was built as shown in Plates 42 and 43, with seals removed from the gate and stainless steel bearings added outside and downstream in the slot area to minimize friction so that only hydraulic loads would be measured. The slide gate was positioned at various gate openings, and a range of discharges were passed through the culvert with the energy gradient immediately upstream of the gate maintained at approximately 46.3 ft (el 725.0) above the culvert invert (el 678.7). The energy gradient was maintained by means of a control gate at the end of the culvert, approximately 142 ft downstream of the slide gate. Details of the gate slot are shown in Plate 43. Plots of the loads listed in Table 16 permit identification of hoist loads for any slide gate operating schedule with appropriate discharges.

54. Hoist loads on the slide gate were measured by means of a force cell mounted as an integral part of the operating strut immediately above the gate pickup point (Figure 17). The force cell output signal was transmitted through a flexible cable, amplified, and recorded




Figure 17. Model test gate installed in test section bulkhead slot




Figure 16. Model control gate, culvert and test section, and headbay tank. Culvert extends 175 ft upstream and 142 ft downstream of slide gate slot




Figure 18. Side view of type 1 (original) slide gate;  
submerged weight 1,814 lb, dry weight 4,209 lb

on a direct-writing recorder. The operating strut was aligned so that the force along the vertical axis was the only significant component. The electrical cable was attached so that it did not contribute lateral forces on the strut or project into the flow stream.

55. Hoist loads on the slide gate to be expected during normal 4-min gate operation simulating the type 5 filling and emptying cycle are plotted in Plates 57 and 58. Similar hoist loads for the type 6 emptying system for a 4-min valve schedule and normal, single (right) and single (left) culvert operations are plotted in Plates 59-61. The discharge curves in Plates 57-61 were computed from filling and emptying data recorded on the 1:25-scale comprehensive model in which the type 5 and 6 filling and emptying systems were reproduced. Under steady-state conditions, no problems with respect to pressure were observed.

56. A very thorough report was drafted on the subject "Filling and Emptying Valves for Lock No. 1, Mississippi River," by representatives

of the NCS. The report included sections concerned with:

- a. Existing conditions
- b. Preliminary investigation
- c. Hydraulic model study
- d. Site inspections
- e. Cost comparisons

Conclusions of the report stated: "There is not enough research or experience to indicate whether or not slide gates will perform satisfactorily as filling and emptying gates at Locks and Dam No. 1. On the other hand, tainter valves have been used successfully at numerous Corps of Engineers locks. Reverse tainter valves meet the highest quality of engineering for new or rehabilitated locks. The additional cost for installation of reverse tainter valves is less than 2 percent of the total project cost, which is well within reason for valves of proven performance, minimum required maintenance, and highest quality. Therefore the St. Paul District has recommended that reverse tainter valves be installed in landward locks to replace the existing stoney gate valves during the rehabilitation of Locks and Dam No. 1."



#### PART IV: DISCUSSION AND RECOMMENDATIONS

57. The existing locks at Locks and Dam No. 1 were constructed between 1929 and 1932. Problems have been experienced with accumulation of ice and debris at the intakes, air entrapment in the culverts of the filling and emptying system, excessive turbulence in the lock chamber during filling, and hazardous conditions downstream from the locks during emptying operations. Also, the stoney gates used for control of filling and emptying, the miter gates, and miter gate operating machinery are in bad condition. Initial investigations and studies indicated that both the landward and riverward locks should be completely rehabilitated. However, later studies recommended that the landward lock be completely rehabilitated and the riverward lock be only partially rehabilitated. Although the riverward lock will not be rehabilitated in the near future, model tests were conducted for both the landward and riverward locks, since those tests had been initiated before the decision was made not to rehabilitate the riverward lock. Also, results of these tests can be used if rehabilitation of the riverward locks becomes feasible in the future.

58. Items that were concerned with improving the hydraulic conditions at the landward lock and recommended from model tests are as follows:

- a. The radius of the nose of the intermediate wall will be increased from 5 ft to 12.5 ft to eliminate vortex tendencies in the upstream approach area.
- b. A new six-port culvert intake manifold will be constructed.
- c. Lowering the existing 9.5-ft-diam culvert invert el 681.2 to invert el 678.7 and changing the culvert shape to 9.5 ft wide by 7.5 ft high resulted in a 1-ft submergence of the culvert roof instead of a 3.5-ft depth of air at the culvert crown at normal lower pool el 687.2.
- d. New sidewall ports 1.5 ft wide by 2.3 ft high will be constructed from the modified 9.5-ft-wide by 7.5-ft-high wall culverts. There will be 19 ports in each culvert spaced 13 ft on centers and staggered in each wall. Because the invert of the culverts is higher than the lock chamber floor, the ports will slope downward. This

slope will extend into the 1-ft-deep trenches in front of each port. The trenches that extend to the center of the lock chamber and terminate vertically are 2.1 ft wide for the land wall ports and 1.88 ft wide for the intermediate wall ports. The difference in width of the trenches is necessary because the port sides expand horizontally on a 1-on-20 slope and the two walls have different thicknesses.

- e. A new culvert outlet will be constructed with interlaced laterals in the lower approach area.
- f. New reverse tainter filling and emptying valves will be installed. These valves should be designed in accordance with the vertically framed tainter valves developed during model tests of the Holt Lock and should be scheduled to open in 4 min.
- g. Twelve-inch-diam air vents will be installed on the center line of the culvert roof about 3.5 ft downstream of the filling and emptying valves. The vents should extend upward to the top of the lock walls and be provided with a control valve which can be locked when set. After the rehabilitation is completed the vents should be adjusted to admit just enough air to preclude cavitation in the low pressure area immediately downstream from the valves without permitting an excessive amount of air and resulting turbulence in the lock chamber. These items were elements of the type 3 system recommended for the landward lock.

59. Rehabilitation of the landward lock as recommended in the type 3 filling and emptying system and operating the culvert tainter valves as recommended will result in a reliable design with satisfactory prototype performance. For normal 37.8-ft head conditions and imposed limitations of 11-ft submergence over the chamber floor and only 1-ft submergence over the sidewall culvert roof at minimum lower pool, the lock can be filled in about 10.2 min or emptied in 10.6 min with a 4-min valve time. In fact, due to differences in friction losses, the prototype lock can be expected to fill or empty about 10 percent faster than the model lock. Longitudinal and transverse hawser forces will be well within the 5-ton limiting criterion for any size tow loaded up to the allowable 9-ft draft. Turbulence in the lock chamber is considered satisfactory and safe for large tows as well as small craft, primarily because of the addition of the trenches in chamber floor at each of the

sidewall ports. There is no indication of any vortex problem in the upstream approach area in the vicinity of the intakes. Flow conditions in the upstream and downstream approaches are good and flow distribution at the intakes and outlets is satisfactory.

60. Since much has been said about the submergence limitations of 11.0 ft, the question of what is the desired submergence in a 56-ft-wide lock with a sidewall port manifold system will be discussed. The greater the submergence, the faster is the permissible filling time. However, in many cases each foot is quite costly and the designer needs to know the minimum submergence at which satisfactory operation can be expected. Data from various width locks indicate that jets from ports expand in an upward direction at the same rate as they expand horizontally. Thus, a clear space between the bottom of the vessel equal to one half the port spacing is required to prevent direct action of the port jets against the bottom of the vessel. In a 56-ft-wide lock designed for 9-ft draft, a submergence of 15.5 ft should be provided (9-ft draft of tow plus 6.5 ft clear under the tow, one half of the 13-ft port spacing). If a greater submergence under the tow is provided, permissible filling times will be shorter; but an increase in clear space under the tow of 100 percent will allow a decrease in permissible filling time of only 10 percent. On the other hand, a decrease in the suggested clear space under the tow of only 20 percent will require a 20 percent increase in permissible filling time. For the case of the landward lock, there was a 69 percent reduction in this desired clearance. This was compensated for, to some degree, by the sloping ports. However, without the port face, port invert extension, and trenches in the chamber floor or some other geometry changes, an acceptable degree of turbulence would have been impossible to obtain. This would have imposed significantly longer filling times for the landward lock. A more thorough treatment of the state of the art and design information on sidewall port lock design is presented in WES Miscellaneous Paper H-75-7.\* The total

---

\* T. E. Murphy, "Lock Design, Sidewall Port Filling and Emptying System," Miscellaneous Paper H-75-7, Jul 1975, U. S. Army Engineer Waterways Experiment Station, CE, Vicksburg, Miss.

culvert and port throat-area ratio, number, spacing, and longitudinal position of the sidewall port manifold in the chamber were based on these design criteria.

61. The invert of the riverward lock chamber is 2.5 ft higher than the landward lock. As a result there is 8.5 ft of submergence in the lock at minimum lower pool and 1 ft of submergence over the culvert roof. Thus, the barge draft must be reduced to 6.5 ft leaving 2 ft of clearance between the barge tow and chamber invert.

62. The same culvert intake design and culvert modifications, including valves and air vents, recommended for the landward lock were recommended for the riverward lock. Since the culverts, ports, and lock chamber were at the same elevation, the sloping ports and chamber trenches were not necessary for the riverward lock; however, the port size, number, and spacing were the same.

63. The culvert outlet with interlaced laterals in the lower approach used in the landward lock would also be satisfactory for the riverward lock. However, if it is desirable to remove a portion of the emptying discharge away from the lower approach of the lock, the separate outlets developed during the model studies could be used.

64. The slide gates investigated in the 1:25-scale model performed satisfactorily with 2- or 4-min valve times. Hoist loads measured in the 1:10-scale model with the slide gate were satisfactory. Little difference in the hydraulic performance of the lock was detected when either tainter valves or slide gates were used. For reasons stated earlier in this report, the culvert tainter valves will be utilized in the landward lock rehabilitation; and the existing stoney valves removed from the existing landward lock will be used as spare gates and for parts to maintain the existing stoney gates for operating the riverward lock where only minimal rehabilitation is planned.

65. With regard to the minimal rehabilitation of the existing riverward lock and the extremely poor operating characteristics and conditions that will of necessity remain, it is suggested that once final plans are prepared, a review be made of possible improvements which might be accomplished at a minimum cost to improve existing conditions.

One such improvement would be to seal the bulkhead slots upstream of the existing stoney valves that presently (in 1976 observations) are one source of air which could be eliminated. There may be other improvements that could be recognized and corrected by economical means.

66. Generalized tests\* were made with the type 6 filling and emptying system for lifts of 30 and 40 ft and submergences of 8.5, 11, 13, and 15 ft over the lock floor. A 6-barge tow at 6.5-ft draft with the upstream end of the tow at sta 0+65 was used to measure hawser forces during filling and emptying with 1-, 2-, and 4-min valve times. Plate 62 is a plot of filling times for 3-, 4-, and 5-ton hawser force limits indicating the effect of submergence and head variations. The filling and emptying times for normal slide gate operation for 30- and 40-ft lifts are also plotted in Plate 62. Hawser forces during all generalized emptying tests were about 3 tons.

---

\* Funded by CWIS Work Unit No. 31076 "Improved Criteria for Lock Design."

Table 1  
Systems Tested and Elements of Systems as Developed

[illegible]

Table 2  
Steady-Flow Pressures in Type 1 (Original) Design Filling System  
Landward Lock

Piezometer					Piezometer				
No.	Station	Elevation	Reading	Pressure	No.	Station	Elevation	Reading	Pressure
<u>Right Wall Culvert</u>					<u>Intermediate Wall Culvert</u>				
<u>Intake to Filling Valve</u>					<u>Ring Downstream of Intake</u>				
1	0+75.50A	708.7	722.5	13.8	25	0+18.50A	708.7 B	713.9	5.2
2	0+70.40A	↓	721.5	12.8	26	↓	713.7 L	713.8	0.1
3	0+65.25A	↓	719.3	10.6	27	↓	718.7 T	714.3	-4.4
4	0+62.20A	↓	717.5	8.8	28	↓	713.7 R	714.0	0.3
5	0+57.00A	↓	716.1	7.4	<u>Ring Downstream of Valve</u>				
6	0+53.90A	↓	715.0	6.3	29	1+10.58B	678.7 B	706.9	28.2
7	0+48.50A	↓	720.3	11.6	30	↓	682.25 L	↓	24.35
8	0+45.80A	↓	718.1	9.4	31	↓	686.2 T	↓	20.4
9	0+40.50A	↓	716.3	7.6	32	↓	682.25 R	↓	24.35
10	0+37.50A	↓	714.8	6.1					
11	0+33.88A	↓	713.8	5.1					
12	0+18.50A	708.7 B	713.6	4.9					
13	↓	713.7 L	713.5	-0.2					
14	↓	718.7 T	714.0	-4.7					
15	↓	713.7 R	713.5	-0.2					
16	0+44.30B	701.7	712.0	10.3					
17	0+46.80B	697.7	712.5	14.8					
18	0+72.33B	686.2	706.2	20.0					
<u>Filling Valve</u>									
19	0+91.45B	686.2	706.5	20.3					
20	1+04.95B	686.2	706.0	19.8					
21	1+09.95B	678.70 B	706.3	27.6					
22	↓	682.25 L	706.2	23.95					
23	↓	686.20 T	705.7	19.5					
24	↓	682.25 R	706.0	23.75					
<u>Sidewall Port Manifold</u>									
1A	1+32.58B	682.45	706.8	24.35					
2A	2+09.58B	↓	709.7	27.25					
3A	3+00.08B	↓	711.6	29.15					
4A	3+73.98B	↓	712.0	29.55					

Note: Pressures are in prototype feet of water. Test conditions: steady-flow discharge, 2868 cfs; upper pool el, 725.0; lock chamber el, 704.5; filling valves open; upper miter gates closed; emptying valves closed; lower miter gates open.

Table 3  
Steady-Flow Pressures in Type 1 (Original) Design Emptying System  
Landward Lock

Piezometer					Piezometer				
No.	Station	Elevation	Reading	Pressure	No.	Station	Elevation	Reading	Pressure
<u>Right Wall Culvert</u>					<u>Right Wall Culvert</u>				
<u>Ring Downstream of Filling Valve</u>					<u>Outlet (Continued)</u>				
21	1+09.95B	678.7 B	705.7	27.0	11	5+50.00B	670.2	689.2	19.0
22	↓	682.45 L	705.7	23.25	12	5+50.00B	670.2	690.2	19.0
23	↓	686.2 1	705.1	19.9	13	5+66.00B	686.2	AIR	
24	↓	682.45 R	705.7	23.25	14	5+78.00B	677.82	684.8	6.98
<u>Sidewall Port Manifold</u>					15	5+82.00B	677.2	691.3	14.1
1B	1+32.58B	680.95	705.5	24.55	16	↓	676.2	690.5	14.3
2B	2+09.58B	↓	705.0	24.05	17	↓	670.2	686.9	16.7
3B	3+00.08B	↓	701.2	20.25	18	↓	↓	686.4	16.2
4B	3+73.98B	↓	695.0	14.05	19	↓	↓	688.1	17.9
<u>Emptying Valve</u>					20	↓	↓	689.2	19.0
1	4+17.87B	686.2	AIR	--	<u>Intermediate Culvert</u>				
2	4+25.87B	↓	691.0	4.8	<u>Ring Downstream of Filling Valve</u>				
3	4+30.87B	↓	690.5	4.3	29	1+10.58B	678.7 B	705.2	26.5
4	4+35.87B	↓	688.5	2.3	30	↓	682.45 L	705.2	22.75
5	4+40.87B	↓	689.5	3.3	31	↓	686.2 T	705.1	18.9
6	4+45.87B	↓	688.0	1.8	32	↓	682.45 R	705.2	22.75
7	4+50.87B	↓	688.5	2.3	<u>Ring Downstream of Emptying Valve</u>				
8	4+70.87B	687.7	688.3	9.6	21	4+70.50E	678.7	688.5	9.8
9	↓	682.45	BAD	--	22	↓	682.45	BAD	--
10	↓	686.2	688.3	2.1	23	↓	686.2	688.5	2.3
11	↓	682.45	688.3	5.85	24	↓	682.45	688.6	6.15
<u>Outlet</u>									
1	5+15.12B	677.82	680.7	2.88					
2	5+18.00B	677.2	690.3	13.1					
3	↓	676.2	688.6	12.4					
4	↓	670.2	686.1	15.9					
5	↓	↓	688.0	17.8					
6	↓	↓	688.3	18.1					
7	↓	↓	689.0	18.8					
8	5+34.00B	686.2	AIR	--					
9	5+50.00B	670.2	687.1	16.9					
10	5+50.00B	670.2	688.6	18.4					

Note: Pressures are in prototype feet of water. Test conditions: steady-flow discharge, 2888 cfs; lock chamber el, 711.2; lower pool el, 687.2; filling valves closed; upper miter gates open; emptying valves open full; lower miter gates closed.



Table 1  
Average Piezometer Readings During Filling Operations, Dye 1 System, F. S. Ft. Bend  
Near Pool E1 725.0, Lower Pool E1 687.2

Piezometer Locations		Average Piezometer Readings in Prototype Feet of Water									
No.	Station	T = 30*		T = 60		T = 90		T = 120		T = 150	
		LC = 687.9**		LC = 688.0		LC = 689.3		LC = 691.1		LC = 693.5	
<b>Right Wall Culvert</b>											
<b>Intake to Filling Valve</b>											
1	0+75.50A	724.9	724.8	724.1	724.0	723.3	723.4	721.7	721.5	721.9	722.3
2	0+70.40A	724.9	724.6	724.0	723.4	722.3	722.0	720.2	720.4	721.1	721.5
3	0+65.25A	724.9	724.5	724.0	723.0	722.3	721.4	719.0	719.1	720.5	721.1
4	0+62.20A	724.9	724.1	723.7	723.0	720.3	719.5	718.9	718.1	719.5	720.5
5	0+57.00A	724.9	724.1	723.6	722.1	719.4	718.9	718.7	718.1	719.5	720.5
6	0+57.00A	724.9	724.3	723.2	722.1	718.4	718.1	717.8	717.1	718.5	719.5
7	0+48.50A	724.9	724.6	724.0	723.0	721.4	720.5	718.6	718.9	720.5	721.1
8	0+44.50A	724.9	724.5	723.8	722.5	720.5	719.6	717.7	718.5	720.1	720.5
9	0+40.50A	724.9	724.1	723.3	722.6	720.5	719.6	717.7	718.5	720.1	720.5
10	0+37.50A	724.9	724.2	723.0	721.0	719.9	718.1	716.5	717.1	718.5	719.5
11	0+33.85A	724.9	724.8	723.1	721.0	719.8	718.1	716.5	717.1	718.5	719.5
12	0+18.50A	724.9	724.1	722.9	721.1	719.8	718.1	716.5	717.1	718.5	719.5
13	0+18.50A	724.9	724.1	722.9	721.1	719.8	718.1	716.5	717.1	718.5	719.5
14	0+18.50A	724.9	724.1	722.9	721.1	719.8	718.1	716.5	717.1	718.5	719.5
15	0+18.50A	724.9	724.1	722.9	721.1	719.8	718.1	716.5	717.1	718.5	719.5
16	0+44.30B	724.9	723.6	722.0	719.3	717.5	716.1	714.4	714.1	715.8	716.5
17	0+46.80B	724.9	723.6	722.3	719.9	718.1	716.1	714.4	714.1	715.8	716.5
18	0+72.33B	724.9	723.3	721.3	717.8	712.5	708.7	703.9	701.8	710.0	713.0
<b>Culvert Invert at Drop</b>											
A	0+30.00B	724.3	723.6	722.3	720.0	716.4	712.7	710.4	711.9	713.3	715.3
B	0+35.00B	724.3	723.5	722.1	719.3	715.3	711.0	708.5	709.4	711.8	713.8
C	0+37.00B	724.3	723.4	721.8	718.5	713.7	708.6	705.6	706.6	709.5	712.1
D	0+39.50B	724.3	723.1	721.7	718.1	713.2	708.5	705.6	706.6	709.5	712.1
E	0+41.25B	724.3	723.1	721.7	715.6	710.2	705.9	701.3	702.3	710.9	713.1
<b>Filling Valve</b>											
19	0+91.45B	686.1	683.1	679.9	677.4	676.9	681.1	689.4	712.2	713.3	715.3
20	1+04.95B	685.2	682.9	678.7	678.1	678.1	681.5	689.5	712.2	713.3	715.3
21	1+04.95B	686.4	683.3	682.3	680.0	682.2	687.5	697.6	712.2	713.3	715.3
22	1+09.95B	686.5	682.6	679.4	678.3	681.7	687.5	697.6	712.2	713.3	715.3
23	1+09.95B	686.2	682.3	679.0	678.3	682.6	687.5	697.6	712.2	713.3	715.3
24	1+09.95B	686.8	684.7	679.7	678.8	682.7	687.5	697.6	712.2	713.3	715.3
<b>Side Wall Port Manifold</b>											
1A	1+32.52B	687.1	687.6	688.1	689.3	692.5	694.2	700.4	704.1	711.2	712.5
2A	2+09.58B	687.0	687.7	688.0	691.4	694.9	698.9	703.5	707.0	714.1	715.9
3A	3+00.08B	687.0	687.5	688.8	691.5	695.3	700.2	705.1	708.6	715.1	716.6
4A	3+73.96B	687.0	687.7	689.2	692.1	696.4	701.5	706.6	710.1	716.6	718.1
<b>Intermediate Wall Culvert</b>											
<b>High Downstream of Intake</b>											
25	0+15.50A	724.7	724.1	723.1	721.2	718.3	715.1	712.6	711.1	717.4	718.5
26	0+15.50A	724.6	724.0	723.0	721.0	718.0	714.5	712.3	710.3	716.6	717.6
27	0+15.50A	724.7	724.1	723.1	721.3	718.4	715.4	712.9	710.9	717.4	718.5
28	0+15.50A	724.8	724.1	723.2	721.3	718.3	715.1	712.6	710.6	717.3	718.4
<b>High Downstream of Valve</b>											
29	1+10.58B	686.8	683.5	681.6	681.9	684.9	691.6	699.6	704.1	711.2	712.5
30	1+10.58B	686.2	683.5	681.5	681.5	685.0	691.6	699.6	704.1	711.2	712.5
31	1+10.58B	686.6	683.5	681.6	681.1	684.8	691.6	699.6	704.1	711.2	712.5
32	1+10.58B	686.7	683.5	681.6	681.6	685.1	691.6	699.6	704.1	711.2	712.5

Note: Lock filled in 10.2 min with h-min valve. The bulkhead studs upstream and downstream of the filling valves were sealed at the roof of the culvert.

\* T denotes time (in prototype seconds) after beginning of valve movement.

\*\* LC denotes elevation of water surface in lock chamber.

Table 5  
Average Metering Readings for the Drilling Station, 3200 ft. Depth, 17 ft. Head  
Upper Pool 11.75 ft. Lower Pool 11.75 ft.

Metering Station	Reading	Average Metering Readings in Various Parts of Meter									
		1-10	11-20	21-30	31-40	41-50	51-60	61-70	71-80	81-90	91-100
Upper Pool 11.75 ft.											
1	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
2	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
3	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
4	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
5	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
6	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
7	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
8	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
9	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
10	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
11	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
Lower Pool 11.75 ft.											
1	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
2	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
3	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
4	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
5	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
6	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
7	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
8	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
9	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
10	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1
11	1.17.00	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1	687.1

Notes: Lock opened in 10.2 min with local valve. The ballheads of emptying valves were open.  
 \* 2 minutes time in (proceeds second) after beginning of valve movement.  
 \*\* 12 minutes duration of water surface in lock chamber.

Table 3  
Average Piezometer Readings During Filling Operation, Type 4 System, 37.8-Ft Head  
Upper Pool El 725.0, Lower Pool El 687.2

Piezometer Locations No. Station Elevation Right, All Culvert	Average Piezometer Readings in Prototype Feet of Water									
	T = 30*	T = 60	T = 90	T = 120	T = 150	T = 180	T = 210	T = 240	T = 270	T = 300
	LC = 687.7**	LC = 688.2	LC = 689.5	LC = 691.2	LC = 693.2	LC = 695.2	LC = 697.1	LC = 701.3	LC = 707.1	LC = 710.4
<b>Intake to Filling Valve</b>										
1 0-75.50A 708.7	724.9	724.8	724.6	724.1	723.5	723.8	723.1	721.7	721.9	722.3
2 0-70.40A 708.7	724.9	724.6	724.3	723.5	722.4	723.5	723.2	721.7	721.2	721.7
3 0-65.20A 708.7	724.9	724.5	724.1	723.0	721.4	721.9	721.2	719.0	718.5	718.7
4 0-62.20A 708.7	724.9	724.4	723.5	722.2	721.1	721.7	721.0	718.1	717.6	717.7
5 0-57.00A 708.7	724.9	724.2	723.4	722.1	720.9	721.0	720.3	717.7	717.2	717.3
6 0-53.90A 708.7	724.9	724.2	723.1	721.0	719.9	720.2	719.3	716.7	716.2	716.3
7 0-48.50A 708.7	724.9	724.6	723.9	723.1	721.9	721.9	721.1	718.2	717.7	717.7
8 0-45.80A 708.7	724.9	724.6	723.1	721.8	721.1	721.2	720.4	717.2	716.7	716.7
9 0-40.20A 708.7	724.9	724.6	723.1	721.8	721.1	721.2	720.4	717.2	716.7	716.7
10 0-37.20A 708.7	724.9	724.6	723.1	721.8	721.1	721.2	720.4	717.2	716.7	716.7
11 0-33.80A 708.7	724.9	724.6	723.1	721.8	721.1	721.2	720.4	717.2	716.7	716.7
12 0-30.80A 708.7	724.9	724.6	723.1	721.8	721.1	721.2	720.4	717.2	716.7	716.7
13 0-28.00A 708.7	724.9	724.6	723.1	721.8	721.1	721.2	720.4	717.2	716.7	716.7
14 0-25.00A 708.7	724.9	724.6	723.1	721.8	721.1	721.2	720.4	717.2	716.7	716.7
15 0-22.00A 708.7	724.9	724.6	723.1	721.8	721.1	721.2	720.4	717.2	716.7	716.7
16 0-18.50A 708.7	724.9	724.6	723.1	721.8	721.1	721.2	720.4	717.2	716.7	716.7
17 0-15.50A 708.7	724.9	724.6	723.1	721.8	721.1	721.2	720.4	717.2	716.7	716.7
18 0-12.33B 686.2	724.9	724.6	723.1	721.8	721.1	721.2	720.4	717.2	716.7	716.7
<b>Culvert Invert at Drop</b>										
A 0-30.00B 708.7	724.3	723.7	722.3	719.9	716.7	713.2	710.7	710.8	712.9	715.2
B 0-27.00B 708.7	724.3	723.6	722.1	719.2	715.6	712.1	709.6	709.1	711.5	713.7
C 0-24.00B 708.7	724.3	723.5	722.6	718.2	713.8	709.2	706.7	706.2	708.6	711.6
D 0-21.00B 708.7	724.3	723.6	722.6	718.2	713.8	709.2	706.7	706.2	708.6	711.6
E 0-18.00B 708.7	724.3	723.6	722.6	718.2	713.8	709.2	706.7	706.2	708.6	711.6
F 0-15.00B 708.7	724.3	723.6	722.6	718.2	713.8	709.2	706.7	706.2	708.6	711.6
G 0-12.00B 708.7	724.3	723.6	722.6	718.2	713.8	709.2	706.7	706.2	708.6	711.6
H 0-9.00B 708.7	724.3	723.6	722.6	718.2	713.8	709.2	706.7	706.2	708.6	711.6
I 0-6.00B 708.7	724.3	723.6	722.6	718.2	713.8	709.2	706.7	706.2	708.6	711.6
J 0-3.00B 708.7	724.3	723.6	722.6	718.2	713.8	709.2	706.7	706.2	708.6	711.6
<b>Filling Valve</b>										
19 0-91.45B 685.2	685.2	682.0	679.0	676.6	675.5	679.9	687.7	701.1	705.2	712.3
20 1-04.95B 685.2	685.2	681.7	678.5	675.3	673.9	680.4	687.6	702.3	706.4	712.3
21 1-09.95B 685.2	685.2	681.7	678.5	675.3	673.9	680.4	687.6	702.3	706.4	712.3
22 1-09.95B 685.2	685.2	681.7	678.5	675.3	673.9	680.4	687.6	702.3	706.4	712.3
23 1-09.95B 685.2	685.2	681.7	678.5	675.3	673.9	680.4	687.6	702.3	706.4	712.3
24 1-09.95B 685.2	685.2	681.7	678.5	675.3	673.9	680.4	687.6	702.3	706.4	712.3
<b>Sidewall Port Manifold</b>										
1A 1-32.58B 682.45	687.5	687.6	687.8	689.7	696.9	696.2	700.7	704.5	707.9	711.0
2A 2-09.48B 682.45	687.5	687.6	687.8	689.7	696.9	696.2	700.7	704.5	707.9	711.0
3A 3-00.08B 682.45	687.5	687.6	687.8	689.7	696.9	696.2	700.7	704.5	707.9	711.0
4A 4-73.98B 682.45	687.5	687.6	687.8	689.7	696.9	696.2	700.7	704.5	707.9	711.0
<b>Intermediate Wall Culvert</b>										
25 0-18.50A 708.7 B	724.8	724.1	722.9	720.6	717.7	714.6	711.8	711.7	713.7	715.7
26 0-18.50A 713.7 L	724.7	724.0	723.0	720.7	717.7	714.6	711.8	711.7	713.7	715.7
27 0-18.50A 718.7 T	724.7	724.0	723.0	720.7	717.7	714.6	711.8	711.7	713.7	715.7
28 0-18.50A 713.7 R	724.7	724.0	723.0	720.7	717.7	714.6	711.8	711.7	713.7	715.7
<b>Blow Downstream of Valve</b>										
29 1-10.58B 678.7 B	684.6	682.8	681.6	682.0	684.7	680.7	688.6	703.1	706.7	710.2
30 1-10.58B 682.25L	685.0	683.0	681.2	681.7	684.2	680.0	687.7	702.1	705.9	709.4
31 1-10.58B 686.2 T	684.7	682.7	681.0	681.5	684.0	680.0	687.7	702.1	705.9	709.4
32 1-10.58B 682.58R	684.3	682.9	681.6	682.0	684.7	680.7	688.6	703.1	706.7	710.2

Note. Lock filled in 9.8 min with 4-min valve. The bulkhead slots upstream and downstream of the filling valves were sealed at the roof of the culvert.

\* T denotes time (in prototype seconds) after beginning of valve movement.

\*\* LC denotes elevation of water surface in lock chamber.

Table 7  
Average Piezometer Readings During Emptying Operation, Type 4 System, 37.8-Ft. Head  
Upper Pool El. 725.0, Lower Pool El. 697.2

Piezometer Locations No. Station Elevation	Average Piezometer Readings in Prototype Feet of Water									
	T = 30*	T = 60	T = 90	T = 120	T = 150	T = 180	T = 210	T = 240	T = 270	T = 300
Right Wall Culvert	LC = 724.9**	LC = 724.4	LC = 723.3	LC = 721.7	LC = 719.7	LC = 716.8	LC = 713.5	LC = 709.7	LC = 706.1	LC = 702.7
Subwall Port. Manifold										
1B 1+32.50B 680.95	724.9	724.2	722.4	720.0	716.4	712.0	707.4	703.6	700.6	696.2
2B 2+09.50B	725.0	724.2	722.6	720.1	716.7	712.2	707.7	703.7	700.5	696.2
3B 3+00.00B	724.7	723.7	721.4	718.6	715.2	710.6	704.3	701.7	698.2	694.7
4B 3+73.90B	724.6	723.2	720.2	716.7	713.1	708.6	704.2	701.7	698.2	694.7
Emptying Valve										
1 1+17.87B 686.2	685.2	680.8	675.9	672.5	670.6	672.0	677.2	686.1	687.3	687.3
2 1+32.50B 684.9	684.9	680.3	675.8	672.5	670.6	672.0	677.2	686.1	687.3	687.3
3 1+47.87B 683.5	683.5	678.9	674.4	671.1	669.2	670.6	675.8	684.7	685.9	685.9
4 1+62.87B 682.1	682.1	677.5	673.0	669.7	667.8	669.2	674.4	683.3	684.5	684.5
5 1+77.87B 680.7	680.7	676.1	671.6	668.3	666.4	667.8	673.0	681.9	683.1	683.1
6 1+92.87B 679.3	679.3	674.7	670.2	666.9	665.0	666.4	671.6	680.5	681.7	681.7
7 1+107.87B 677.9	677.9	673.3	668.8	665.5	663.6	665.0	670.2	679.1	680.3	680.3
8 1+122.87B 676.5	676.5	671.9	667.4	664.1	662.2	663.6	668.8	677.7	678.9	678.9
9 1+137.87B 675.1	675.1	670.5	666.0	662.7	660.8	662.2	667.4	676.3	677.5	677.5
10 1+152.87B 673.7	673.7	669.1	664.6	661.3	659.4	660.8	666.0	674.9	676.1	676.1
11 1+167.87B 672.3	672.3	667.7	663.2	659.9	658.0	659.4	664.6	673.5	674.7	674.7
Outlet										
1 5+15.17B 677.82	687.2	687.2	686.3	683.2	683.2	681.2	677.0	680.7	680.7	680.7
2 5+18.00B 677.2	687.8	687.8	686.9	683.8	683.8	681.8	677.6	681.3	681.3	681.3
3 5+20.83B 676.2	687.4	687.4	686.5	683.4	683.4	681.4	677.2	680.9	680.9	680.9
4 5+23.66B 675.2	687.0	687.0	686.1	683.0	683.0	681.0	676.8	680.5	680.5	680.5
5 5+26.49B 674.2	687.5	687.5	686.6	683.5	683.5	681.5	677.3	681.0	681.0	681.0
6 5+29.32B 673.2	687.1	687.1	686.2	683.1	683.1	681.1	676.9	680.6	680.6	680.6
7 5+32.15B 672.2	687.6	687.6	686.7	683.6	683.6	681.6	677.4	681.1	681.1	681.1
8 5+34.98B 671.2	687.1	687.1	686.2	683.1	683.1	681.1	676.9	680.6	680.6	680.6
9 5+37.81B 670.2	687.5	687.5	686.6	683.5	683.5	681.5	677.3	681.0	681.0	681.0
10 5+40.64B 669.2	687.9	687.9	687.0	683.9	683.9	681.9	677.7	681.4	681.4	681.4
11 5+43.47B 668.2	687.3	687.3	686.4	683.3	683.3	681.3	677.1	680.8	680.8	680.8
12 5+46.30B 667.2	687.7	687.7	686.8	683.7	683.7	681.7	677.5	681.2	681.2	681.2
13 5+49.13B 666.2	687.1	687.1	686.2	683.1	683.1	681.1	676.9	680.6	680.6	680.6
14 5+51.96B 665.2	687.5	687.5	686.6	683.5	683.5	681.5	677.3	681.0	681.0	681.0
15 5+54.79B 664.2	687.9	687.9	687.0	683.9	683.9	681.9	677.7	681.4	681.4	681.4
16 5+57.62B 663.2	687.3	687.3	686.4	683.3	683.3	681.3	677.1	680.8	680.8	680.8
17 5+60.45B 662.2	687.7	687.7	686.8	683.7	683.7	681.7	677.5	681.2	681.2	681.2
18 5+63.28B 661.2	687.1	687.1	686.2	683.1	683.1	681.1	676.9	680.6	680.6	680.6
19 5+66.11B 660.2	687.5	687.5	686.6	683.5	683.5	681.5	677.3	681.0	681.0	681.0
20 5+68.94B 659.2	687.9	687.9	687.0	683.9	683.9	681.9	677.7	681.4	681.4	681.4
Intermediate Wall Culvert										
21 1+70.50B 678.7 B	687.8	687.8	686.9	683.8	683.8	681.8	677.6	681.3	681.3	681.3
22 1+70.50B 677.7 B	687.4	687.4	686.5	683.4	683.4	681.4	677.2	680.9	680.9	680.9
23 1+70.50B 676.7 B	687.8	687.8	686.9	683.8	683.8	681.8	677.6	681.3	681.3	681.3
24 1+70.50B 675.7 B	687.2	687.2	686.3	683.2	683.2	681.2	677.0	680.7	680.7	680.7

Note: Lock empties in 9.9 min with 4-min valve. The bulkheads at emptying valves open.  
\* T denotes time (in prototype seconds) after beginning of valve movement.  
\*\* LC denotes elevation of water surface in lock chamber.

Table 8

Average Piezometer Readings During Filling Operation, Type 5 (with Slide Gates) System, 37.8-Ft Head  
Upper Pool El 725.0, Lower Pool El 687.2

Piezometer Locations		Average Piezometer Readings in Prototype Feet of Water													
No. Station Elevation		T = 30*	T = 60	T = 90	T = 120	T = 150	T = 180	T = 210	T = 240	T = 300	T = 360	T = 420	T = 540	T = 600	
Right Wall Culvert		LC = 687.7**	LC = 688.6	LC = 690.1	LC = 692.4	LC = 695.3	LC = 698.5	LC = 702.0	LC = 705.6	LC = 709.1	LC = 711.9	LC = 714.6	LC = 718.8	LC = 726.1	
Intake to Filling Valve															
1	0+75.50A	724.8	724.5	724.0	722.2	722.8	722.0	721.9	722.0	722.5	723.2	723.4	723.9	724.2	725.0
2	0+76.40A	724.8	724.2	723.5	722.8	721.8	721.0	720.5	720.5	721.6	722.5	724.1	724.7	724.7	725.0
3	0+77.20A	724.9	724.1	723.5	722.7	721.0	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
4	0+78.00A	725.0	724.0	723.5	722.7	721.0	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
5	0+78.80A	725.0	724.0	723.5	722.7	721.0	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
6	0+79.60A	724.6	723.5	723.0	722.0	720.5	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
7	0+80.40A	724.9	724.2	723.5	722.7	721.0	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
8	0+81.20A	724.8	723.5	723.0	722.0	720.5	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
9	0+82.00A	724.6	723.5	723.0	722.0	720.5	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
10	0+83.00A	724.5	723.3	722.8	721.8	720.5	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
11	0+84.00A	724.5	723.3	722.8	721.8	720.5	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
12	0+85.00A	724.5	723.3	722.8	721.8	720.5	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
13	0+86.00A	724.5	723.3	722.8	721.8	720.5	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
14	0+87.00A	724.5	723.3	722.8	721.8	720.5	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
15	0+88.00A	724.5	723.3	722.8	721.8	720.5	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
16	0+89.00A	724.5	723.3	722.8	721.8	720.5	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
17	0+90.00A	724.3	722.7	722.0	721.4	720.5	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1
18	0+91.00A	724.1	722.2	721.2	720.5	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1	725.1
18-A	0+92.00A	724.0	722.0	721.0	720.5	719.0	718.5	718.5	719.6	720.8	721.6	722.7	724.5	725.1	725.1
Culvert Invert Drop															
A	0+30.00B	708.7	722.8	720.5	717.7	715.0	712.5	711.7	712.6	715.0	718.7	720.2	719.7	724.1	725.0
B	0+31.00B	708.7	722.6	720.5	716.9	713.5	710.8	710.0	711.0	713.5	716.0	718.0	719.7	724.0	725.0
C	0+32.00B	708.7	722.0	719.1	715.5	711.5	708.2	707.2	708.4	711.6	714.2	716.5	718.5	723.9	724.9
C-T	0+33.00B	708.7	722.0	721.0	718.6	716.5	714.3	714.0	714.8	716.6	718.3	721.0	723.0	724.3	725.0
T-1	0+34.00B	708.7	722.1	721.2	718.9	716.7	714.6	714.2	715.0	716.9	718.3	721.0	723.0	724.3	725.0
T-2	0+35.00B	708.17	722.1	721.6	718.2	716.0	714.2	713.9	714.6	716.0	717.4	720.0	721.8	724.0	725.0
T-3	0+36.00B	708.17	722.2	721.5	716.0	712.9	709.8	709.1	710.3	713.0	715.4	717.3	719.1	722.9	724.0
T-4	0+37.00B	708.08	722.2	721.5	716.0	712.9	709.8	709.1	710.3	713.0	715.4	717.3	719.1	722.9	724.0
Filling Valve															
19	0+87.00B	686.2	679.2	676.3	676.2	674.5	686.0	694.0	706.2	709.6	712.8	715.3	717.7	723.6	725.0
20	0+88.00B	686.2	678.5	675.5	675.5	674.0	687.6	694.0	706.1	709.5	712.7	715.2	717.7	723.6	725.0
21	1+00.00B	686.2	679.5	676.8	676.8	675.0	688.2	694.0	706.4	709.7	712.8	715.2	717.7	723.6	725.0
22	1+00.00B	686.2	679.5	676.8	676.8	675.0	688.2	694.0	706.4	709.7	712.8	715.2	717.7	723.6	725.0
23	1+00.00B	686.2	679.5	676.8	676.8	675.0	688.2	694.0	706.4	709.7	712.8	715.2	717.7	723.6	725.0
24	1+00.00B	686.2	679.5	676.8	676.8	675.0	688.2	694.0	706.4	709.7	712.8	715.2	717.7	723.6	725.0
25	1+05.00B	686.2	679.5	676.8	676.8	675.0	688.2	694.0	706.4	709.7	712.8	715.2	717.7	723.6	725.0
26	1+10.00B	686.2	681.0	681.2	685.0	691.2	697.6	702.0	705.6	709.0	712.3	715.4	717.4	723.6	725.0
Sidewall Port Manifold															
1A	1+32.50B	682.5	688.4	690.7	693.2	696.4	701.0	705.0	708.4	711.5	714.2	716.5	718.3	723.7	725.1
2A	2+09.00B	687.9	689.4	692.0	695.1	699.0	703.5	707.2	710.6	713.1	715.5	717.3	719.0	723.8	725.1
3A	3+00.00B	687.5	689.1	691.8	695.4	700.0	705.0	708.9	712.0	714.7	717.1	718.9	720.3	724.1	725.0
4A	3+73.90B	687.5	689.2	692.0	695.7	700.4	705.5	709.3	712.4	714.9	717.0	718.6	720.0	723.9	725.0
5A	4+05.50B	687.6	689.1	692.0	695.7	700.4	705.5	709.3	712.4	714.9	717.0	718.5	720.0	723.9	725.0
Intermediate Wall Culvert															
Ring Downstream of Filling Valve															
27	0+18.50B	708.7 B	722.7	720.4	717.5	715.0	712.6	712.2	713.5	715.5	717.4	718.9	720.4	724.1	725.0
28	0+18.50B	718.7 T	722.6	720.2	717.3	714.5	712.2	712.0	713.0	715.3	717.1	718.9	720.3	724.1	725.0
29	0+18.50B	718.7 T	723.4	721.4	718.5	715.9	713.1	712.2	712.8	714.7	716.8	718.8	720.0	723.9	725.0
30	0+18.50B	713.7 R	722.8	720.4	717.5	714.7	712.2	711.9	713.0	715.3	717.1	718.8	720.3	724.1	725.0
Ring Downstream of Filling Valve															
31	1+00.00B	678.7 B	680.2	678.1	678.8	684.8	694.5	702.9	706.5	709.8	713.0	715.1	717.9	721.2	725.0
32	1+00.00B	682.1 B	678.2	676.7	677.2	683.2	690.0	700.2	705.8	709.3	712.5	714.7	717.7	721.0	725.0
33	1+00.00B	686.2 T	678.3	675.8	676.9	683.2	690.0	700.2	705.8	709.3	712.5	714.7	717.7	721.0	725.0

Table 9  
Average Piezometer Readings During Emptying Operation, Type 5 (with Slide Gates) Systems, 37.8-Ft. Head  
Upper Pool El. 725.0, Lower Pool El. 687.2

Piezometer Locations No. Station Elevation	Average Piezometer Readings in Prototype Feet of Water									
	T = 30* LC = 724.7**	T = 60 LC = 724.0	T = 90 LC = 722.6	T = 120 LC = 720.4	T = 150 LC = 718.1	T = 180 LC = 715.1	T = 210 LC = 711.9	T = 240 LC = 708.3	T = 270 LC = 705.1	T = 300 LC = 702.0
<b>Right Wall Culvert</b>										
<b>Sidewall Port Manifold</b>										
1B 1-32.50B 690.95	725.0	723.5	721.5	718.5	713.8	710.3	705.1	702.3	699.5	697.0
2B 2-09.00B 690.95	725.0	723.5	721.5	718.5	713.8	710.3	705.1	702.3	699.5	697.0
3B 3-00.00B 690.95	724.8	723.0	720.4	718.0	711.5	707.5	702.8	698.8	694.5	691.8
4B 4-73.90B 690.95	724.4	722.0	718.8	714.4	707.5	702.8	698.8	694.5	691.8	689.0
5B 5-05.50B 690.95	724.2	721.5	717.6	712.5	704.3	699.0	694.4	689.0	683.1	687.9
<b>Culvert Slide Gate</b>										
1 4-65.50B 678.7 B	724.2	721.3	718.0	713.0	704.5	698.8	691.5	688.8	687.7	687.2
2 4-65.50B 682.45L	724.1	721.4	717.7	712.5	703.9	698.3	691.2	687.8	687.6	687.2
3 4-65.50B 686.2 T	724.0	721.0	717.0	711.7	703.0	697.4	690.5	687.0	686.3	686.3
4 4-65.50B 682.45R	724.0	721.0	717.0	711.7	703.0	697.4	690.5	687.0	686.3	686.3
5 4-65.50B 686.2	724.0	721.0	717.0	711.7	703.0	697.4	690.5	687.0	686.3	686.3
6 5-01.75B 686.2	724.0	721.0	717.0	711.7	703.0	697.4	690.5	687.0	686.3	686.3
7 5-01.75B 686.2	724.0	721.0	717.0	711.7	703.0	697.4	690.5	687.0	686.3	686.3
8 5-01.75B 686.2	724.0	721.0	717.0	711.7	703.0	697.4	690.5	687.0	686.3	686.3
<b>Outlet</b>										
1 5-18.10B 677.82	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
2 5-18.10B 677.2	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
3 5-18.10B 676.2	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
4 5-18.10B 670.2	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
5 5-18.10B 670.2	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
6 5-18.10B 670.2	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
7 5-18.10B 678.7	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
8 5-18.10B 670.2	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
9 5-18.10B 670.2	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
10 5-18.10B 670.2	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
11 5-18.10B 678.7	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
12 5-18.10B 670.2	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
13 5-18.10B 678.7	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
14 5-18.10B 670.2	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
15 5-18.10B 678.7	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
16 5-18.10B 670.2	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
17 5-18.10B 678.7	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
18 5-18.10B 670.2	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
19 5-18.10B 678.7	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
20 5-18.10B 670.2	687.0	686.5	685.8	687.1	687.4	687.2	688.0	682.0	682.0	685.0
<b>Intermediate Wall Culvert</b>										
<b>Sidewall Port Manifold</b>										
21 4-65.50 678.7 B	724.0	720.8	716.3	710.0	701.0	695.5	689.5	687.4	687.2	687.2
22 4-65.50 682.45L	723.9	720.5	716.0	708.5	700.5	695.2	689.1	687.4	687.2	687.2
23 4-65.50 686.2 T	723.9	720.7	716.2	710.5	701.8	696.5	690.4	688.5	687.2	687.2
24 4-65.50 682.45R	723.9	720.7	716.2	710.5	701.8	696.5	690.4	688.5	687.2	687.2

Note: Lock empties in 9.0 min with 4-min valve (constant speed gate opening). The bulkhead starts emptying at 9.0 min. T denotes time (in prototype seconds).

Table 10  
Visual Observations of Water Surface in Bulkhead Slots  
Immediately Upstream of Slide Gates During  
Filling and Emptying Operations  
Type 5 System

<u>Slide Gate Operation</u>	Valve	Upstream Bulkhead Slot	
	Time, $V_t$ min	Water-Surface El ft, msl	Time of Occurrence min*
<u>Normal Filling</u>	2	701.0	2.2
	4	706.0	3.8
	6	710.0	5.2
	8	712.0	6.0
<u>Normal Emptying</u>	2	686.2**	2.0
	4	686.2**	3.4
	6	686.2**	5.1
	8	686.2**	7.0
<u>Single (Right) Culvert</u>			
<u>Filling</u>	2	695.0	1.5
	4	697.2	4.1
	6	702.5	6.2
	8	705.0	7.3
<u>Single (Right) Culvert</u>			
<u>Emptying</u>	2	686.2**	1.9
	4	686.2**	3.2
	6	686.2**	5.4
	8	686.2**	7.1

Note: Initial conditions 37.8-ft head (upper pool el 725.0, lower pool el 687.2). Slide gates open at constant speed. Bulkhead slots downstream of slide gates sealed at roof of culvert.

\* Time after slide gates begin opening.

\*\* Roof of culverts at el 686.2

Table 11  
Steady-Flow Pressures in Type 6 Design Emptying System  
Riverwood Lock

Piezometer					Piezometer				
No.	Station	Elevation	msl Reading	Pressure	No.	Station	Elevation	msl Reading	Pressure
<u>Intermediate Wall (Right Culvert)</u>					<u>Riverward Wall (Left Culvert)</u>				
<u>Sidewall Port Manifold</u>					<u>Sidewall Port Manifold</u>				
1B	1+32.58	680.95	701.8	20.85	1C	1+32.58	680.95	701.2	20.25
2B	2+09.08	↓	701.6	20.65	2C	2+09.08	↓	701.0	20.05
3B	3+00.08	↓	699.4	18.45	3C	3+00.08	↓	697.5	16.55
4B	3+73.98	↓	694.5	13.45	4C	3+73.98	↓	691.5	10.55
<u>Culvert Slide Gate</u>					<u>Culvert Slide Gate</u>				
1	3+91.50	686.2	690.1	3.9	1	4+13.50	678.7 B	685.5	6.80
2	4+00.50	686.2	690.0	3.8	2	4+13.50	682.45 L	685.5	3.05
3	4+08.50	686.2	689.8	3.6	3	4+13.50	686.2 T	685.0	-1.2
4	4+13.50	687.7 B	691.5	12.8	4	4+65.5	678.7 B	683.7	5.0
5	4+13.50	682.45 R	689.7	7.25	5	4+65.5	686.2 T	683.7	-2.5
6	4+13.50	686.2 T	↓	3.5	<u>Outlet</u>				
7	4+18.50	686.2	↓	3.5	1	4+94.00	678.7 B	684.8	6.1
8	4+23.50	686.2	↓	3.5	2	4+94.00	686.2 T	684.7	-1.5
9	4+65.50	678.7 B	688.7	10.0	3	4+94.00	675.5 B	684.4	8.9
10	4+65.50	686.2 T	688.7	2.5	4	4+89.25	678.2 R	684.3	6.1
<u>Outlet</u>					5	4+94.00	682.97 T	684.0	1.03
1	5+11.50	678.7	687.5	8.8	6	4+98.75	678.2 L	684.3	6.1
2	5+11.50	686.2	687.9	1.7	7	4+95.90	675.0	686.7	11.7
3	5+25.20	677.9	678.8	0.9	8	5+04.40	↓	687.2	12.2
4	5+29.00	677.2	689.7	12.5	9	5+01.60	↓	685.8	10.8
5	↓	674.1	690.2	16.1	10	4+98.80	↓	685.4	10.4
6	↓	672.2	686.2	14.0	11	4+95.60	↓	686.0	11.0
7	↓	↓	687.7	15.2	12	4+95.00	↓	686.7	11.7
8	↓	↓	688.3	16.1	13	4+94.10	↓	686.7	11.7
9	↓	↓	689.0	16.8					
10	5+57.20	677.9	687.5	9.6					
11	5+61.00	677.2	689.8	12.6					
12	↓	674.1	689.8	15.7					
13	↓	672.2	687.0	14.8					
14	↓	↓	687.5	15.3					
15	↓	↓	688.1	15.9					
16	↓	↓	688.5	16.3					

Note: Pressures are in prototype feet of water. Test conditions: steady-flow discharge, 2970 cfs; lock chamber el, 707.2; lower pool el, 687.2; filling slide gate closed; upper miter gates open; emptying slide gates open; lower miter gate closed.



Table 12  
Average Piezometer Readings During Normal Slide Gate Operating Operations, Type 6 System, K. Ball, Road  
Upper Pool El. 725.0, Lower Pool El. 687.2  
Riverward Lock

Piezometer Locations		Average Piezometer Readings in Prototype Feet of Water									
Box Station	Elevation	T = 30	T = 60	T = 90	T = 120	T = 150	T = 180	T = 210	T = 240	T = 270	T = 300
Intermediate Well (Right)		LC = 724.7									
1B 1424.508	680.0	724.0	724.7	724.8	724.9	725.0	725.1	725.2	725.3	725.4	725.5
2B 1425.508	680.0	724.1	724.8	724.9	725.0	725.1	725.2	725.3	725.4	725.5	725.6
3B 1426.508	680.0	724.2	724.9	725.0	725.1	725.2	725.3	725.4	725.5	725.6	725.7
4B 1427.508	680.0	724.3	725.0	725.1	725.2	725.3	725.4	725.5	725.6	725.7	725.8
5B 1428.508	680.0	724.4	725.1	725.2	725.3	725.4	725.5	725.6	725.7	725.8	725.9
6B 1429.508	680.0	724.5	725.2	725.3	725.4	725.5	725.6	725.7	725.8	725.9	726.0
7B 1430.508	680.0	724.6	725.3	725.4	725.5	725.6	725.7	725.8	725.9	726.0	726.1
8B 1431.508	680.0	724.7	725.4	725.5	725.6	725.7	725.8	725.9	726.0	726.1	726.2
9B 1432.508	680.0	724.8	725.5	725.6	725.7	725.8	725.9	726.0	726.1	726.2	726.3
10B 1433.508	680.0	724.9	725.6	725.7	725.8	725.9	726.0	726.1	726.2	726.3	726.4
Outlet		LC = 687.2									
1 1434.508	686.2	687.0	687.7	687.8	687.9	688.0	688.1	688.2	688.3	688.4	688.5
2 1435.508	686.2	687.1	687.8	687.9	688.0	688.1	688.2	688.3	688.4	688.5	688.6
3 1436.508	686.2	687.2	687.9	688.0	688.1	688.2	688.3	688.4	688.5	688.6	688.7
4 1437.508	686.2	687.3	688.0	688.1	688.2	688.3	688.4	688.5	688.6	688.7	688.8
5 1438.508	686.2	687.4	688.1	688.2	688.3	688.4	688.5	688.6	688.7	688.8	688.9
6 1439.508	686.2	687.5	688.2	688.3	688.4	688.5	688.6	688.7	688.8	688.9	689.0
7 1440.508	686.2	687.6	688.3	688.4	688.5	688.6	688.7	688.8	688.9	689.0	689.1
8 1441.508	686.2	687.7	688.4	688.5	688.6	688.7	688.8	688.9	689.0	689.1	689.2
9 1442.508	686.2	687.8	688.5	688.6	688.7	688.8	688.9	689.0	689.1	689.2	689.3
10 1443.508	686.2	687.9	688.6	688.7	688.8	688.9	689.0	689.1	689.2	689.3	689.4
Outlet		LC = 650.0									
1 1444.508	686.2	650.0	650.7	650.8	650.9	651.0	651.1	651.2	651.3	651.4	651.5
2 1445.508	686.2	650.1	650.8	650.9	651.0	651.1	651.2	651.3	651.4	651.5	651.6
3 1446.508	686.2	650.2	650.9	651.0	651.1	651.2	651.3	651.4	651.5	651.6	651.7
4 1447.508	686.2	650.3	651.0	651.1	651.2	651.3	651.4	651.5	651.6	651.7	651.8
5 1448.508	686.2	650.4	651.1	651.2	651.3	651.4	651.5	651.6	651.7	651.8	651.9
6 1449.508	686.2	650.5	651.2	651.3	651.4	651.5	651.6	651.7	651.8	651.9	652.0
7 1450.508	686.2	650.6	651.3	651.4	651.5	651.6	651.7	651.8	651.9	652.0	652.1
8 1451.508	686.2	650.7	651.4	651.5	651.6	651.7	651.8	651.9	652.0	652.1	652.2
9 1452.508	686.2	650.8	651.5	651.6	651.7	651.8	651.9	652.0	652.1	652.2	652.3
10 1453.508	686.2	650.9	651.6	651.7	651.8	651.9	652.0	652.1	652.2	652.3	652.4
Outlet		LC = 612.8									
1 1454.508	618.7	613.0	613.7	613.8	613.9	614.0	614.1	614.2	614.3	614.4	614.5
2 1455.508	618.7	613.1	613.8	613.9	614.0	614.1	614.2	614.3	614.4	614.5	614.6
3 1456.508	618.7	613.2	613.9	614.0	614.1	614.2	614.3	614.4	614.5	614.6	614.7
4 1457.508	618.7	613.3	614.0	614.1	614.2	614.3	614.4	614.5	614.6	614.7	614.8
5 1458.508	618.7	613.4	614.1	614.2	614.3	614.4	614.5	614.6	614.7	614.8	614.9
6 1459.508	618.7	613.5	614.2	614.3	614.4	614.5	614.6	614.7	614.8	614.9	615.0
7 1460.508	618.7	613.6	614.3	614.4	614.5	614.6	614.7	614.8	614.9	615.0	615.1
8 1461.508	618.7	613.7	614.4	614.5	614.6	614.7	614.8	614.9	615.0	615.1	615.2
9 1462.508	618.7	613.8	614.5	614.6	614.7	614.8	614.9	615.0	615.1	615.2	615.3
10 1463.508	618.7	613.9	614.6	614.7	614.8	614.9	615.0	615.1	615.2	615.3	615.4
Outlet		LC = 575.6									
1 1464.508	618.7	575.6	576.3	576.4	576.5	576.6	576.7	576.8	576.9	577.0	577.1
2 1465.508	618.7	575.7	576.4	576.5	576.6	576.7	576.8	576.9	577.0	577.1	577.2
3 1466.508	618.7	575.8	576.5	576.6	576.7	576.8	576.9	577.0	577.1	577.2	577.3
4 1467.508	618.7	575.9	576.6	576.7	576.8	576.9	577.0	577.1	577.2	577.3	577.4
5 1468.508	618.7	576.0	576.7	576.8	576.9	577.0	577.1	577.2	577.3	577.4	577.5
6 1469.508	618.7	576.1	576.8	576.9	577.0	577.1	577.2	577.3	577.4	577.5	577.6
7 1470.508	618.7	576.2	576.9	577.0	577.1	577.2	577.3	577.4	577.5	577.6	577.7
8 1471.508	618.7	576.3	577.0	577.1	577.2	577.3	577.4	577.5	577.6	577.7	577.8
9 1472.508	618.7	576.4	577.1	577.2	577.3	577.4	577.5	577.6	577.7	577.8	577.9
10 1473.508	618.7	576.5	577.2	577.3	577.4	577.5	577.6	577.7	577.8	577.9	578.0
Outlet		LC = 538.4									
1 1474.508	618.7	538.4	539.1	539.2	539.3	539.4	539.5	539.6	539.7	539.8	539.9
2 1475.508	618.7	538.5	539.2	539.3	539.4	539.5	539.6	539.7	539.8	539.9	540.0
3 1476.508	618.7	538.6	539.3	539.4	539.5	539.6	539.7	539.8	539.9	540.0	540.1
4 1477.508	618.7	538.7	539.4	539.5	539.6	539.7	539.8	539.9	540.0	540.1	540.2
5 1478.508	618.7	538.8	539.5	539.6	539.7	539.8	539.9	540.0	540.1	540.2	540.3
6 1479.508	618.7	538.9	539.6	539.7	539.8	539.9	540.0	540.1	540.2	540.3	540.4
7 1480.508	618.7	539.0	539.7	539.8	539.9	540.0	540.1	540.2	540.3	540.4	540.5
8 1481.508	618.7	539.1	539.8	539.9	540.0	540.1	540.2	540.3	540.4	540.5	540.6
9 1482.508	618.7	539.2	539.9	540.0	540.1	540.2	540.3	540.4	540.5	540.6	540.7
10 1483.508	618.7	539.3	540.0	540.1	540.2	540.3	540.4	540.5	540.6	540.7	540.8
Outlet		LC = 501.2									
1 1484.508	618.7	501.2	501.9	502.0	502.1	502.2	502.3	502.4	502.5	502.6	502.7
2 1485.508	618.7	501.3	502.0	502.1	502.2	502.3	502.4	502.5	502.6	502.7	502.8
3 1486.508	618.7	501.4	502.1	502.2	502.3	502.4	502.5	502.6	502.7	502.8	502.9
4 1487.508	618.7	501.5	502.2	502.3	502.4	502.5	502.6	502.7	502.8	502.9	503.0
5 1488.508	618.7	501.6	502.3	502.4	502.5	502.6	502.7	502.8	502.9	503.0	503.1
6 1489.508	618.7	501.7	502.4	502.5	502.6	502.7	502.8	502.9	503.0	503.1	503.2
7 1490.508	618.7	501.8	502.5	502.6	502.7	502.8	502.9	503.0	503.1	503.2	503.3
8 1491.508	618.7	501.9	502.6	502.7	502.8	502.9	503.0	503.1	503.2	503.3	503.4
9 1492.508	618.7	502.0	502.7	502.8	502.9	503.0	503.1	503.2	503.3	503.4	503.5
10 1493.508	618.7	502.1	502.8	502.9	503.0	503.1	503.2	503.3	503.4	503.5	503.6
Outlet		LC = 464.0									
1 1494.508	618.7	464.0	464.7	464.8	464.9	465.0	465.1	465.2	465.3	465.4	465.5
2 1495.508	618.7	464.1	464.8	464.9	465.0	465.1	465.2	465.3	465.4	465.5	465.6
3 1496.508	618.7	464.2	464.9	465.0	465.1	465.2	465.3	465.4	465.5	465.6	465.7
4 1497.508	618.7	464.3	465.0	465.1	465.2	465.3	465.4	465.5	465.6	465.7	465.8
5 1498.508	618.7	464.4	465.1	465.2	465.3	465.4	465.5	465.6	465.7	465.8	465.9
6 1499.508	618.7	464.5	465.2	465.3	465.4	465.5	465.6	465.7	465.8	465.9	466.0
7 1500.508	618.7	464.6	465.3	465.4	465.5	465.6	465.7	465.8	465.9	466.0	466.1
8 1501.508	618.7	464.7	465.4	465.5	465.6	465.7	465.8	465.9	466.0	466.1	466.2
9 1502.508	618.7	464.8	465.5	465.6	465.7	465.8	465.9	466.0	466.1	466.2	466.3
10 1503.508	618.7	464.9	465.6	465.7	465.8	465.9	466.0	466.1	466.2	466.3	466.4
Outlet		LC = 426.8									
1 1504.508	618.7	426.8	427.5	427.6	427.7	427.8	427.9	428.0	428.1	428.2	428.3
2 1505.508	618.7	426.9	427.6	427.7	427.8	427.9	428.0	428.1	428.2	428.3	428.4
3 1506.508	618.7	427.0	427.7	427.8	427.9	428.0	428.1	428.2	428.3	428.4	428.5
4 1507.508	618.7	427.1	427.8	427.9	428.0	428.1	428.2	428.3	428.4	428.5	428.6
5 1508.508	618.7	427.2	427.9	428.0	428.1	428.2	428.3	428.4	428.5	428.6	428.7
6 1509.508	618.7	427.3	428.0	428.1	428.2	428.3	428.4	428.5	428.6	428.7	428.8
7 1510.508	618.7	427.4	428.1	428.2	428.3	428.4	428.5	428.6	428.7	428.8	428.9
8 1511.508											

Table 13  
Average Piezometer Readings During Single (Right) Culvert Slide Gate Emptying Operation, Type 6 System, 27.8-in. Head  
Upper Pool at 72.5 ft, Lower Pool at 687.2  
Riverward Lock

Piezometer Locations Sta. Station Elevation	Average Piezometer Readings in Piezometer Feet of Water									
	T = 100 LC = 724.4	T = 150 LC = 723.2	T = 200 LC = 721.9	T = 250 LC = 717.3	T = 300 LC = 710.5	T = 400 LC = 707.2	T = 500 LC = 704.1	T = 600 LC = 699.0	T = 700 LC = 695.0	T = 800 LC = 690.7
<b>Intermediate Wall (Right)</b>										
<b>General Left Hand Side</b>										
18 1-32.508	725.0	719.4	713.5	707.9	702.1	699.8	697.5	693.6	690.8	687.0
28 2-07.088	724.6	718.2	712.0	706.5	701.8	699.5	697.2	693.3	690.7	687.1
48 3-71.988	723.7	717.7	711.5	705.8	700.2	697.9	695.6	691.7	689.0	685.4
<b>Culvert Slide Gate</b>										
1 3-01.508	722.7	717.7	711.7	706.1	700.5	698.2	695.9	692.0	689.2	685.4
2 4-00.508	721.6	716.4	710.4	704.8	699.2	696.9	694.6	690.7	687.9	684.1
3 5-00.508	720.5	715.2	709.2	703.6	698.0	695.7	693.4	689.5	686.7	682.9
4 6-00.508	719.4	714.1	708.1	702.5	696.9	694.6	692.3	688.4	685.6	681.8
5 7-00.508	718.3	713.0	707.0	701.4	695.8	693.5	691.2	687.3	684.5	680.7
6 8-00.508	717.2	711.9	705.9	700.3	694.7	692.4	690.1	686.2	683.4	679.6
7 9-00.508	716.1	710.8	704.8	699.2	693.6	691.3	689.0	685.1	682.3	678.5
8 10-00.508	715.0	709.7	703.7	698.1	692.5	690.2	687.9	684.0	681.2	677.4
9 11-00.508	713.9	708.6	702.6	697.0	691.4	689.1	686.8	682.9	680.1	676.3
10 12-00.508	712.8	707.5	701.5	695.9	690.3	688.0	685.7	681.8	679.0	675.2
<b>Culvert</b>										
1 13-00.508	687.5	687.8	687.8	687.4	686.5	686.2	685.1	684.3	683.4	682.5
2 14-00.508	686.7	687.0	687.0	686.6	685.7	685.4	684.3	683.5	682.6	681.7
3 15-00.508	685.9	686.2	686.2	685.8	684.9	684.6	683.5	682.7	681.8	680.9
4 16-00.508	685.0	685.3	685.3	684.9	684.0	683.7	682.6	681.8	680.9	680.0
5 17-00.508	684.1	684.4	684.4	684.0	683.1	682.8	681.7	680.9	680.0	679.1
6 18-00.508	683.2	683.5	683.5	683.1	682.2	681.9	680.8	680.0	679.1	678.2
7 19-00.508	682.3	682.6	682.6	682.2	681.3	681.0	680.0	679.1	678.2	677.3
8 20-00.508	681.4	681.7	681.7	681.3	680.4	680.1	679.0	678.2	677.3	676.4
9 21-00.508	680.5	680.8	680.8	680.4	679.5	679.2	678.1	677.3	676.4	675.5
10 22-00.508	679.6	679.9	679.9	679.5	678.6	678.3	677.2	676.4	675.5	674.6
11 23-00.508	678.7	679.0	679.0	678.6	677.7	677.4	676.3	675.5	674.6	673.7
12 24-00.508	677.8	678.1	678.1	677.7	676.8	676.5	675.4	674.6	673.7	672.8
13 25-00.508	676.9	677.2	677.2	676.8	675.9	675.6	674.5	673.7	672.8	671.9
14 26-00.508	676.0	676.3	676.3	675.9	675.0	674.7	673.6	672.8	671.9	671.0
15 27-00.508	675.1	675.4	675.4	675.0	674.1	673.8	672.7	671.9	671.0	670.1
16 28-00.508	674.2	674.5	674.5	674.1	673.2	672.9	671.8	671.0	670.1	669.2

Note: Lock filled in 2 min with 4-in valve. The bulkhead slot's downstream of the emptying slide gates were sealed at the root of the culvert.  
 \* T denotes time (in piezometer seconds) after beginning of valve movement.  
 \*\* LC denotes elevation of water surface in lock chamber.

Table 14  
Average Piezometer Readings During Single (Left) Culvert Slide Gate Raising Operation, Dye 6 System, at 8.45 Head  
Upper Pool El. 755.0, Lower Pool El. 697.2  
Riverwall Lock

Piezometer Locations		T = 60	T = 90	T = 120	T = 150	T = 180	T = 210	T = 240	T = 270	T = 300	T = 360	T = 420	T = 480	T = 540	T = 600	T = 660	T = 720	T = 780	T = 840	T = 900
No. Station Elevation		LC = 724.0	LC = 724.0	LC = 724.0	LC = 724.0	LC = 724.0	LC = 718.1	LC = 716.2	LC = 714.1	LC = 712.0	LC = 709.9	LC = 706.1	LC = 702.1	LC = 698.5	LC = 695.0	LC = 691.5	LC = 688.0	LC = 684.5	LC = 681.0	LC = 677.5
River wall (left)																				
Specialized Port Moulds																				
1C 1-77.58h 680.99		724.7	724.8	722.0	719.5	716.1	713.6	709.1	706.4	704.4	703.0	700.3	697.2	694.5	691.8	689.1	686.4	683.7	681.0	678.3
2C 2-402.58h		724.7	724.8	722.0	719.5	716.1	713.6	709.1	706.4	704.4	703.0	700.3	697.2	694.5	691.8	689.1	686.4	683.7	681.0	678.3
3C 3-91.48h		724.7	724.8	722.0	719.5	716.1	713.6	709.1	706.4	704.4	703.0	700.3	697.2	694.5	691.8	689.1	686.4	683.7	681.0	678.3
4C 4-73.58h		724.7	724.8	722.0	719.5	716.1	713.6	709.1	706.4	704.4	703.0	700.3	697.2	694.5	691.8	689.1	686.4	683.7	681.0	678.3
Culvert slide gate																				
1 1-13.40h 678.7 R		684.0	678.9	673.4	670.6	671.0	677.1	681.6	683.7	683.8	684.2	684.7	685.2	685.7	686.2	686.7	687.2	687.7	688.2	688.7
2 2-13.40h 686.45L		684.0	678.9	673.4	670.6	671.0	677.1	681.6	683.7	683.8	684.2	684.7	685.2	685.7	686.2	686.7	687.2	687.7	688.2	688.7
3 3-13.40h 686.45L		684.0	678.9	673.4	670.6	671.0	677.1	681.6	683.7	683.8	684.2	684.7	685.2	685.7	686.2	686.7	687.2	687.7	688.2	688.7
4 4-13.40h 686.45L		684.0	678.9	673.4	670.6	671.0	677.1	681.6	683.7	683.8	684.2	684.7	685.2	685.7	686.2	686.7	687.2	687.7	688.2	688.7
5 5-13.40h 686.45L		684.0	678.9	673.4	670.6	671.0	677.1	681.6	683.7	683.8	684.2	684.7	685.2	685.7	686.2	686.7	687.2	687.7	688.2	688.7
Outlet																				
1 1-94.00h 678.7 R		687.7	687.7	687.2	686.6	685.5	684.5	683.8	683.9	683.2	681.2	681.1	681.0	680.9	680.8	680.7	680.6	680.5	680.4	680.3
2 2-94.00h 686.2 F		687.7	687.7	687.2	686.6	685.5	684.5	683.8	683.9	683.2	681.2	681.1	681.0	680.9	680.8	680.7	680.6	680.5	680.4	680.3
3 3-94.00h 678.2 R		687.7	687.7	687.2	686.6	685.5	684.5	683.8	683.9	683.2	681.2	681.1	681.0	680.9	680.8	680.7	680.6	680.5	680.4	680.3
4 4-94.00h 682.977		687.7	687.7	687.2	686.6	685.5	684.5	683.8	683.9	683.2	681.2	681.1	681.0	680.9	680.8	680.7	680.6	680.5	680.4	680.3
5 5-94.00h 678.2 L		687.7	687.7	687.2	686.6	685.5	684.5	683.8	683.9	683.2	681.2	681.1	681.0	680.9	680.8	680.7	680.6	680.5	680.4	680.3
6 6-94.00h 675.0		687.7	687.7	687.2	686.6	685.5	684.5	683.8	683.9	683.2	681.2	681.1	681.0	680.9	680.8	680.7	680.6	680.5	680.4	680.3
7 7-94.00h 687.4		687.7	687.7	687.2	686.6	685.5	684.5	683.8	683.9	683.2	681.2	681.1	681.0	680.9	680.8	680.7	680.6	680.5	680.4	680.3
8 8-94.00h 687.3		687.7	687.7	687.2	686.6	685.5	684.5	683.8	683.9	683.2	681.2	681.1	681.0	680.9	680.8	680.7	680.6	680.5	680.4	680.3
9 9-94.00h 687.3		687.7	687.7	687.2	686.6	685.5	684.5	683.8	683.9	683.2	681.2	681.1	681.0	680.9	680.8	680.7	680.6	680.5	680.4	680.3
10 10-94.00h 687.3		687.7	687.7	687.2	686.6	685.5	684.5	683.8	683.9	683.2	681.2	681.1	681.0	680.9	680.8	680.7	680.6	680.5	680.4	680.3
11 11-94.00h 687.3		687.7	687.7	687.2	686.6	685.5	684.5	683.8	683.9	683.2	681.2	681.1	681.0	680.9	680.8	680.7	680.6	680.5	680.4	680.3
12 12-94.00h 687.3		687.7	687.7	687.2	686.6	685.5	684.5	683.8	683.9	683.2	681.2	681.1	681.0	680.9	680.8	680.7	680.6	680.5	680.4	680.3
13 13-94.00h 687.3		687.7	687.7	687.2	686.6	685.5	684.5	683.8	683.9	683.2	681.2	681.1	681.0	680.9	680.8	680.7	680.6	680.5	680.4	680.3

Note: 1. Look filled in 15 min with hand valve. The bulb and plate downstream of the regulating slide valve were ejected at the end of the culvert.  
2. T denotes time (in prototype seconds) after beginning of valve closure.  
3. LC denotes elevation of water surface in lock chamber.

Table 15  
Visual Observations of Water Surface in Bulkhead Slots Immediately Upstream  
of Slide Gates During Emptying Operations

Type 6 System

Emptying Operation	Valve Time, V <sub>t</sub> min	Minimum Water-Surface El ft msl	Time of Occurrence min*	Remarks
<u>Normal (Both Culverts)</u>				
Right	2	686.2**	3.3	
	4		4.1	
	6		7.7	
	8		11.6	
Left	2		2.1	Air is entrained
	4		3.8	
	6		10.6	
	8		11.6	
<u>Single (Right) Culvert</u>				
	2		11.7	
	4		11.7	
	6		11.7	
	8		12.5	
<u>Single (Left) Culvert</u>				
	2		2.0	Severe air entrained 3 min til 5 min
	4		4.0	Air is entrained for 2 min til 6 min
	6		5.8	Air is entrained for 1.2 min til 7 min
	8		7.5	

Note: Initial conditions 37.8-ft head (upper pool el 725.0, lower pool el 687.2). Slide gates open at constant speed. Bulkhead slots downstream of slide gates sealed at roof of culvert.

\* Time after slide gate begins opening.

\*\* Roof of culverts at el 686.2.

Table 16


## 1:10-Scale Model Tests, Lock No. 1 Slide Gate

## Hoist Loads, Type 1 (Original) Slide Gate


Slide Gate Open Percent	Feet	Culvert Discharge, cfs		Total Hoist Load, Kips		Slide Gate Open Percent	Feet	Culvert Discharge, cfs		Total Hoist Load, Kips	
		Low	Observed Average	High				Low	Observed Average	High	
10	0.75	100	2.7	2.8		60	4.50	900	4.6	5.1	
		150	3.1	3.2				1050	5.9	6.5	
		200	3.5	3.6				1200	6.9	7.6	
		250	3.9	4.0				1350	7.7	8.3	
		300	4.4	4.6				1500	8.2	9.1	
20	1.50	200	2.7	2.8		70	5.25	1050	3.9	4.5	
		300	4.1	4.2				1200	4.7	5.4	
		400	5.5	5.6				1400	5.6	6.4	
		500	6.9	7.1				1500	6.0	6.9	
								1600	6.6	7.4	
30	2.25	350	3.1	3.2		80	6.00	1100	2.4	2.8	
		500	4.9	5.1				1250	2.9	3.4	
		650	6.7	7.1				1400	3.3	4.0	
		700	7.5	7.9				1550	3.9	4.5	
								1700	4.3	5.0	
40	3.00	500	3.7	3.9		90	6.75	1300	1.1	1.3	
		650	5.0	5.6				1400	1.7	2.1	
		800	7.2	7.5				1500	2.0	2.4	
		950	8.1	8.6				1600	2.1	2.5	
		1100	8.8	9.3				1800	2.2	2.6	
50	3.75	750	4.4	4.7		100	7.50	1300	1.1	1.4	
		900	6.5	6.9				1400	1.7	2.1	
		1050	7.2	8.1				1500	2.0	2.4	
		1200	8.8	9.4				1600	2.2	2.5	
		1350	9.6	10.2				1700	2.2	2.6	

Note: Energy elevation immediately upstream from culvert slide gate was maintained at approximately 46.3 ft (el 725.0) above the culvert invert (el 678.7). Submerged weight of gate is 1,814 lb (1.814 kips). Dry weight of gate is 4,209 lb (4.209 kips). Culvert 8 ft wide by 7.5 ft high.


PHOTOGRAPHS



a. Before filling started




b. 2 min after filling started



c. 4 min after filling started

Photo 1. Surface currents in approach during filling operation with type 1 (original) intake and approach, type 2 intermediate wall pier nose, 4-min valve time; upper pool el 725.0, lock chamber el 687.2  
(sheet 1 of 2)



d. 6 min after filling started




e. 8 min after filling started




f. 10 min after filling started

Photo 1. (sheet 2 of 2)





a. Before filling started




b. 2 min after filling started



c. 4 min after filling started


Photo 2. Surface currents in lock chamber during filling operation with type 1 (original) design, 4-min valve time, 11-ft submergence; upper pool el 725.0, lower chamber el 687.2 (sheet 1 of 2)



d. 6 min after filling started



e. 8 min after filling started



f. 10 min after filling started


Photo 2. (sheet 2 of 2)



a. Before filling started




b. 2 min after filling started




c. 8 min after filling started


Photo 3. Surface currents in lock chamber during filling operation with type 2 sidewall port manifold design, 4-min valve time, 11-ft submergence; upper pool el 725.0, lower chamber el 687.2 (sheet 1 of 2)



d. 6 min after filling started




e. 8 min after filling started




f. 10 min after filling started


Photo 3. (sheet 2 of 2)



a. Before filling started




b. 2 min after filling started




c. 4 min after filling started


Photo 4. Surface currents in lock chamber during filling operation with type 3 sidewall port manifold design, 4-min valve time, 11-ft submergence; upper pool el 725.0, lower pool el 687.2 (sheet 1 of 2)



d. 6 min after filling started




e. 8 min after filling started




f. 10 min after filling started


Photo 4. (sheet 2 of 2)



a. Before filling started



b. 2 min after filling started



c. 4 min after filling started


Photo 5. Surface currents in lock chamber during filling operation with type 4 sidewall port manifold design, 4-min valve time, 11-ft submergence; upper pool el 727.5, lower pool el 689.7 (sheet 1 of 2)



d. 6 min after filling started




e. 8 min after filling started




f. 10 min after filling started

Photo 5. (sheet 2 of 2)





a. Before filling started



b. 2 min after filling started




c. 4 min after filling started


Photo 6. Surface currents in lock chamber during filling operation with type 4 sidewall port manifold design, 5-min valve time, 8.5-ft submergence, riverward lock conditions; upper pool el 725.0, lower pool el 687.2 (sheet 1 of 2)



d. 6 min after filling started



e. 8 min after filling started




f. 10 min after filling started

Photo 6. (sheet 2 of 2)




a. Normal culvert operation




b. Single (right)  
culvert operation

Photo 7. Flow conditions during peak discharge with type 2 outlets for riverward lock installed, 4-min valve; initial lock chamber el 725.0, lower pool el 687.2 (sheet 1 of 2)



c. Single (left) culvert operation

Photo 7. (sheet 2 of 2)








PLATE 1

2











PLAN




# EXISTING LOCK STRUCTURE PLAN

















**EXISTING LOCK STRUCTURE**  
**TRANSVERSE SECTION**  
**SHEET 2**





SCALP  $\theta = 20^\circ$








PLATE 6








PLAN




PLAN



SECTION C-C

INTERMEDIATE WALL  
BOTH LOCKS REHABILITATED



SECTION D-D

RIVER WALL

Scale 1"=5'-0"




HYDRAULIC IMPROVEMENTS  
INTAKE MANIFOLDS

WALL  
LIMITED ONLY

# LEGEND:

Proposed structures




# LEGEND


Proposed structures

Alternate A:  
E outlet conduit and stilling basin  
for river well discharges

Alternate B:  
E outlet conduit for  
river well discharges





## SECTION C-C



## PROPOSED MODIFICATIONS PLAN 4


## SECTION B-B






SECTION A-A  
VALVE OMITTED

SCALE IN FEET




SIDE VIEW

TAINTER VALVE




SECTION B-B (FROM PLATE 3)  
REVISED CULVERTS AND PORTS


SCALE IN FEET





### KEY PLAN




SECTION THROUGH PORT





PORT DETAIL - INTERMEDIATE WALL




SECTION THROUGH PORT




PORT DETAIL - LAND WALL



SECTION B-B (FROM PLATE 3)  
REVISED CULVERTS AND PORTS




## HYDRAULIC IMPROVEMENTS TAINTER VALVES, CULVERTS AND PORTS












PLAN




SECTION C-C



SECTION B-B



SECTION A-A




Scale: 1" = 10' 0"


# HYDRAULIC IMPROVEMENTS DOWNSTREAM STRUCTURES PLANS 1, 2, 3, & 4

2






UPSTREAM PLAN




DOWNSTREAM PLAN

NOTE: FOR RIVERWARD LOCK TEST THE DOWNSTREAM TOPOGRAPHY WAS SHIFTED AS SHOWN IN PLATE 50.



LANDWARD LOCK  
TOPOGRAPHY



TYPE B BARGE

TYPE A BARGE


NO. OF BARGES	BARGE TYPES		DISPLACEMENT, TONS	
	A	B	9-FT DRAFT	6.5-FT DRAFT
6(1-6)	4	2	4844	3472
3(1-3)	2	1	2422	1736
2(1&4)	2		1560	1128

# DETAILS OF BARGES AND BARGE TOWS LANDWARD LOCK TOW DRAFT 9.0 FT RIVERWARD LOCK TOW DRAFT 6.5 FT







# CULVERT AND PORT SECTION TYPE I (ORIGINAL) SYSTEM





**PLATE 17**









CULVERT TAINTER VALVE  
VERSUS SLIDE GATE  
OPENING SCHEDULE



### VELOCITIES AT PORT FACE



### FLOW DISTRIBUTION

NOTE: VELOCITIES ARE IN PROTOTYPE FEET PER SECOND AND ARE MEASURED AT WALL FACE OF INTAKE MANIFOLDS.

### TEST CONDITIONS

TOTAL DISCHARGE 2868 CFS  
UPPER POOL EL 725.0  
LOCK CHAMBER EL 704.5  
FILLING VALVES OPEN FULL  
UPPER MITER GATES CLOSED  
EMPTYING VALVES CLOSED  
LOWER MITER GATES OPEN


## INTAKE MANIFOLD VELOCITIES AND FLOW DISTRIBUTION TYPE I (ORIGINAL) SYSTEM STEADY-FLOW CONDITION



TOP OF LOCK WALL EL 738.7

MITER GATE  
EL 718.7

NOTE PIEZ. A-E WERE ADDED FOR  
TYPE 3 SYSTEM TESTS  
PIEZ. C&C WERE ADDED FOR  
TYPE 4 SYSTEM TESTS




FILLING PIEZOMETERS FILLING VALVE ELEVATION



FILLING PIEZOMETERS SIDEWALL PORT MANIFOLD

FILLING PLAN

NOTE: IN SECTION THROUGH SIDEWALL PORT MANIFOLD  
THE CULVERT, PORT, AND CHAMBER FLOOR ARE  
AT A COMMON INVERT EL 678.7 IN THE TYPE 4  
SYSTEM

TOP OF LOWER LOCK WALL EL 709.7










SYMBOL	VALVE TIME, MIN
$\Delta$	2
$\square$	4
$\nabla$	6
$\circ$	8

### CULVERT ROOF PRESSURES DOWNSTREAM OF FILLING AND EMPTYING VALVES

2-, 4-, 6-, AND 8-MIN VALVE TIMES

TYPE I (ORIGINAL) SYSTEM

37.8-FT HEAD (UPPER POOL EL 725.0, LOWER POOL EL 687.2)  
LANDWARD LOCK



VALVE TIME, MIN


2	4	6
---	---	---

SYMBOL

△	□	○
---	---	---


1 FT WATER ON CULVERT ROOF (LOWER POOL 6882)  
 3 FT WATER ON CULVERT ROOF (NORMAL LOWER POOL 6872)

# MAXIMUM HAWSER FORCES DURING FILLING AND EMPTYING OPERATIONS NORMAL VS 2-FT INCREASE IN LOWER POOL ELEVATION TYPE 1 (ORIGINAL) SYSTEM 378-FT HEAD LANDWARD LOCK



#### VELOCITIES AT PORT FACE

NOTE VELOCITIES ARE IN PROTOTYPE FEET PER SECOND  
AND ARE MEASURED AT WALL FACE OF OUTLET PORTS



TEST CONDITIONS

TOTAL DISCHARGE 2888 CFS

LOCK CHAMBER EL 711.2

LOWER POOL EL 678.2

FILLING VALVES CLOSED


UPPER MITER GATES OPEN

EMPTYING VALVES OPEN FULL


LOWER MITER GATES CLOSED

#### OUTLET VELOCITIES AND FLOW DISTRIBUTION TYPE 1 (ORIGINAL) SYSTEM STEADY-FLOW CONDITION LANDWARD LOCK





LOCK FILLING AND EMPTYING TIMES  
TYPE 1 (ORIGINAL) VS TYPE 2 SYSTEMS  
LANDWARD LOCK  
378-FT HEAD (UPPER POOL EL 725.0, LOWER POOL EL 687.2)






TYPE	PORT DEFLECTORS DIMENSIONS, FT	
	LENGTH, L	HEIGHT, H
1	6	2
2	4	2
3	3	2
4	4	1

NOTE: VISUAL OBSERVATIONS OF TURBULENCE AND INITIAL PORT JET PATTERNS WERE MADE WITH THE TYPE 1 (ORIGINAL) PORT AND MANIFOLD ARRANGEMENT AND PORT DEFLECTORS TYPES 1-4 INSTALLED.

THE TYPE 1 (ORIGINAL) PORT AND MANIFOLD DESIGN WITH TYPE 4 PORT DEFLECTORS WAS DESIGNATED TYPE 2 SIDEWALL PORT MANIFOLD ARRANGEMENT

# DETAILS OF TYPE I (ORIGINAL) PORTS AND PORT DEFLECTORS TYPES 1-4 LANDWARD LOCK



SYMBOL	VALVE TIME, MIN
△	2
□	4
○	6
◇	8

**MAXIMUM HAWSER FORCES DURING FILLING AND EMPTYING OPERATIONS**






TYPE 1 (ORIGINAL) VS

TYPE 2 SIDEWALL PORT SYSTEMS

37.8-FT HEAD

LANDWARD LOCK









SYMBOL	VALVE TIME, MIN	NO. BARGES	BOY STATION
△	2	0	0+65
○	4	2	0+65
—	6	2	3+05

# MAXIMUM HAWSER FORCES DURING FILLING AND EMPTYING OPERATIONS


TYPE 4 SYSTEM

37.8-FT HEAD (UPPER POOL EL 727.5,  
LOWER POOL EL 689.7)

6- AND 2-BARGE TOWS AT 9-FT DRAFT  
LANDWARD LOCK



#### EMPTYING OPERATIONS



#### LEGEND

- 11-FT SUBMERGENCE, 9-FT TOW DRAFT
- - - 8.5-FT SUBMERGENCE, 6.5-FT TOW DRAFT



SYMBOL	VALVE TIME MIN
Δ	2
□	4
▽	6
○	8

### MAXIMUM HAWSER FORCES DURING FILLING AND EMPTYING OPERATIONS

SINGLE (RIGHT) VALVE  
TIMES 2, 4, 6, AND 8 MIN

TYPE 4 SYSTEM

37.8-FT HEAD, 8.5-FT SUBMERGENCE, 6.5-FT DRAFT  
VERSUS  
37.8-FT HEAD, 11.0-FT SUBMERGENCE, 9-FT DRAFT



SYMBOL	VALVE TIME MIN	INITIAL CULVERT ROOF SUBMERGENCE, FT
$\Delta$	2	3.5
$\square$	4	
$\nabla$	6	
$\circ$	8	
$\blacktriangle$	2	10
$\blacksquare$	4	
$\blacktriangledown$	6	
$\bullet$	8	


LEGEND  
 — OBSERVED AVERAGE  
 --- HIGH  
 - - - LOW

### CULVERT ROOF PRESSURES DOWNSTREAM OF FILLING AND EMPTYING VALVES


NORMAL AND SINGLE (RIGHT)  
VALVE OPERATIONS

TYPE 4 SYSTEM

11-FT SUBMERGENCE, LOWER POOL EL 689.7  
8.5-FT SUBMERGENCE, LOWER POOL EL 687.2  
37.9-FT HEAD







NOTE: 11-FT SUBMERGENCE, OR MINIMUM LOWER POOL ABOVE LOCK CHAMBER FLOOR DURING THESE TESTS. THUS FOR TYPE SIDEWALL PORT MANIFOLD DESIGN II WAS NECESSARY TO ADD 2.5 FT ADDITIONAL DEPTH TO UPPER AND LOWER POOLS




LEGEND  
 TYPE 1  
 TYPE 2  
 TYPE 3  
 TYPE 4

# LOCK FILLING AND EMPTYING TIME VS VALVE TIME TYPES 1 (ORIGINAL), 2, 3, AND 4 SYSTEMS LANDWARD LOCK 378-FT HEAD











SYMBOL	VALVE TIME, MIN	SIDEWALL PORT MANIFOLD TYPE
Δ	2	1
○	4	2
▽	6	3
○	8	4
---		
---		
---		



**MAXIMUM HAWSER FORCES DURING FILLING AND EMPTYING OPERATIONS**  
 TYPES 1 (ORIGINAL), 2, 3, AND 4  
 SIDEWALL PORT SYSTEM  
 11-FT MINIMUM SUBMERGENCE OVER LOCK FLOOR  
 378-FT HEAD  
 LANDWARD LOCK







CULVERT ROOF PRESSURES DOWNSTREAM  
OF FILLING AND EMPTYING VALVES  
TYPE 3 SYSTEM  
37.8-FT HEAD (UPPER POOL EL 725.0, LOWER POOL EL 687.2)




# MAXIMUM HAWSER FORCES DURING FILLING AND EMPTYING OPERATIONS

TYPE 3 SYSTEM

37.8-FT HEAD (UPPER POOL EL 725.0,  
LOWER POOL EL 687.2)  
6- AND 2-BARGE TOWS AT 9-FT DRAFT  
LANDWARD LOCK



#### EMPTYING OPERATIONS




#### FILLING OPERATIONS

SYMBOL	VALVE TIME MIN
Δ	2
□	4
▽	6
○	8



### MAXIMUM HAWSER FORCES DURING FILLING AND EMPTYING OPERATIONS

SINGLE (RIGHT) VALVE  
TIMES 2, 4, 6, AND 8 MIN

TYPE 3 SYSTEM  
378-FT HEAD (UPPER POOL EL 725.0,  
LOWER POOL EL 687.2)  
6-BARGE TOW AT 9-FT DRAFT  
LANDWARD LOCK



SYMBOL	VALVE OPENING, MIN	VALVE POSITION, MIN	VALVE TO FULL, MIN
$\times$	2.0	2.0	2.0
$\circ$	1.75	2.0	2.25
$\Delta$	1.50	2.0	2.50



LEGEND

— OBSERVED AVERAGE






--- HIGH

--- LOW

EFFECT OF DELAYED  
VALVE OPERATIONS ON  
MAXIMUM HAMMER FORCES  
FULL TOW AND CULVERT  
ROOF PRESSURES  
DOWNSTREAM OF FILLING  
AND EMPTYING VALVES

TYPE 3 SYSTEM  
37.6-FT HEAD (UPPER POOL EL 725.0, LOWER POOL EL 687.2)  
LANDWARD LOCK










SYMBOL	VALVE TIME, MIN	NO. BARGES	BOW STATION
○	2	6	0+65
□	4	2	0+85
△	6	2	3+05

**MAXIMUM HAWSER FORCES DURING FILLING AND EMPTYING OPERATIONS**

TYPE 4 SYSTEM





378-FT HEAD (UPPER POOL EL 725.0,  
LOWER POOL EL 687.2)

6- AND 2-BARGE TOWS AT 65-FT DRAFT  
RIVERWARD LOCK




**MAXIMUM HAWSER FORCES DURING FILLING AND EMPTYING OPERATIONS**  
 NORMAL 2-, 4-, 6-, AND 8-MIN VALVES  
 TYPE 4 SYSTEM, RIVERWARD LOCK  
 FULL VS HALF TOW AT 6.5-FT DRAFT,  
 8.5-FT(MIN) SUBMERGENCE  
 37.8-FT HEAD (UPPER POOL EL 725.0,  
 LOWER POOL EL 687.2)





#### EMPTYING OPERATIONS




#### FILLING OPERATIONS

SYMBOL	VALVE TIME, MIN	NO. BARGES	BOW STATION
△	2		
□	4		
▽	6		
○	8		
—	FULL TOW	60-6)	0+85
- - -	HALF TOW	3(1-3)	0+85


#### MAXIMUM HAWSER FORCES DURING FILLING AND EMPTYING OPERATIONS

SINGLE (RIGHT) VALVE  
TIMES 2, 4, 6, AND 8 MIN


TYPE 4 SYSTEM, RIVERWARD LOCK  
FULL VS HALF TOW AT 6.5-FT DRAFT  
8.5-FT(MIN) SUBMERGENCE  
37.8-FT HEAD (UPPER POOL EL 725.0,  
LOWER POOL EL 687.2)



SECTION A-A  
SCALE:  $\frac{3}{4}$ " = 1'-0"




UPSTREAM ELEVATION  
SCALE:  $\frac{3}{4}$ " = 1'-0"



DETAIL A  
SCALE:  $\frac{3}{4}$ " = 1'-0"

CI 1307


Detail A



SECTION B-B  
SCALE:  $\frac{3}{4}$ " = 1'-0"

CI 1307

Detail B




DETAIL A  
SCALE:  $\frac{3}{4}$ " = 1'-0"




DETAIL C  
SCALE:  $\frac{3}{4}$ " = 1'-0"


1' 0"



SECTION B-B  
SCALE:  $\frac{1}{2}$ " = 1'-0"




DETAIL A  
SCALE: 3/4" = 1'-0"










DETAIL C  
SCALE: 3/4" = 1'-0"


General Notes  
Gate to be welded air-tight and to be filled with  
mortar.  
Est. gate wt - 4400 lb.




SLIDE GATE

2







SECTION E-E  
SCALE 1 1/2"=1'-0"



SECTION C-C  
SCALE 3"=1'-0"




SECTION F-F  
SCALE 3"=1'-0"




DETAIL A  
SCALE 3"=1'-0"

Shims as required




SECTION D-D  
SCALE 3"=1'-0"

El 6757



SECTION G-G  
SCALE 1 1/2"=1'-0"




SECTION J-J  
SCALE FULL SIZE




SLIDE GATE  
EMBEDDED PARTS






ELEVATION INTAKE THRU FILLING SLIDE GATE




PLAN FILLING SYSTEM



PLAN EMPTYING SYSTEM


## PIEZOMETER LOCATIONS TYPE 5 SYSTEM WITH CULVERT SLIDE GATES

2




**LOCK FILLING AND EMPTYING TIMES  
VS SLIDE GATE TIME**  
NORMAL AND SINGLE (RIGHT)  
GATE OPERATIONS  
TYPE 5 SYSTEM  
378-FT HEAD, 8.5-FT SUBMERGENCE, LOWER POOL EL 687.2





#### FILLING OPERATIONS



#### EMPTYING OPERATIONS

**LEGEND**  
 — OBSERVED AVERAGE  
 - - - HIGH  
 - - - LOW






SYMBOL	SLIDE GATE TIME, MIN.
Δ	2
□	4
▽	6
○	8

NOTE: SLIDE GATE OPENING SCHEDULE  
 CONSTANT SPEED.  
 BULKHEAD SLOTS DOWNSTREAM OF FILLING  
 AND EMPTYING SLIDE GATES SEALED.

### MINIMUM CULVERT ROOF PRESSURES DOWNSTREAM OF FILLING AND EMPTYING SLIDE GATES DURING NORMAL AND SINGLE GATE OPERATIONS

TYPE 5 SYSTEM





37.8-FT HEAD, 8.5-FT SUBMERGENCE, LOWER POOL EL 667.2




SYMBOL	SLIDE GATE TIME, MIN	NO. BARGES	BOW STATION
△	2	6(1-6)	0+65
○	4	2(184)	0+85
▽	6	2(346)	3+05
—	8		

NOTE: SLIDE GATE OPENING SCHEDULE  
CONSTANT SPEED.  
BULKHEAD SLOTS DOWNSTREAM OF FILLING  
AND EMPTYING SLIDE GATES SEALED

# MAXIMUM HAWSER FORCES DURING FILLING AND EMPTYING OPERATIONS NORMAL 2-, 4-, 6-, AND 8-MIN SLIDE GATE OPERATIONS TYPE 5 SYSTEM 8.5-FT SUBMERGENCE, LOWER POOL EL 6872 37.8-FT HEAD



#### EMPTYING OPERATIONS



#### FILLING OPERATIONS

SYMBOL	SLIDE GATE TIME, MIN	NO. BARGES	BOW STATION
Δ	2		
□	4		
▽	6		
○	8		


NOTE: SLIDE GATE OPENING SCHEDULE  
CONSTANT SPEED.  
BULKHEAD SLOTS DOWNSTREAM OF FILLING  
AND EMPTYING SLIDE GATES SEALED.


#### MAXIMUM HAWSER FORCES DURING FILLING AND EMPTYING OPERATIONS

SINGLE (RIGHT) SLIDE  
GATE 2, 4, 6, AND 8 MIN

TYPE 5 SYSTEM

8.5-FT SUBMERGENCE, LOWER POOL EL 6872  
37.8-FT HEAD






PLAN


SCALE  
 0 25 50 75 100 FT

TAILBAY TOPOGRAPHY  
 TYPE 6 EMPTYING SYSTEM  
 RIVERWARD LOCK




NOTE: VELOCITIES ARE IN PROTOTYPE FEET PER SECOND AND ARE MEASURED AT WALL FACE OF PORTS.

# OUTLET VELOCITIES AND FLOW DISTRIBUTION TYPE 2 DESIGN INTERMEDIATE WALL OUTLET STEADY-FLOW DISCHARGE RIVERWARD LOCK



## VELOCITY DISTRIBUTION AT LATERAL PORT WALL FACE RIGHT CULVERT, INTERMEDIATE WALL RIVERWARD LOCK


TEST CONDITIONS  
TOTAL DISCHARGE (PEAK STEADY FROM 4'-MIN NORMAL) 2985 CFS  
PERCENT DISCHARGE INTERMEDIATE (RIGHT WALL) OUTLET 43.2  
PERCENT DISCHARGE RIVERWARD LOCK WALL OUTLET 56.8  
LOCK CHAMBER EL 707.2  
LOWER POOL EL 687.2  
FILLING VALVES AND LOWER MITER GATES CLOSED  
EMPTYING VALVES AND UPPER MITER GATES OPEN



VELOCITY DISTRIBUTION AT OUTLET PORT WALL FACE  
LEFT CULVERT, RIVERWARD LOCK

### TEST CONDITIONS

	2985 CFS
TOTAL DISCHARGE (PEAK STEADY FROM 4 MIN NORMAL)	4...2
PERCENT DISCHARGE INTERMEDIATE WALL OUTLET	56.8
PERCENT DISCHARGE RIVERWARD LOCK WALL OUTLET	7072
LOCK CHAMBER EL	
LOWER POOL EL	6872
FILLING VALVES AND LOWER MITER GATES CLOSED	
EMPTYING VALVES AND UPPER MITER GATES OPEN	



### OUTLET FLOW DISTRIBUTION


NOTE: VELOCITIES ARE IN PROTOTYPE FEET PER SECOND  
AND ARE MEASURED AT WALL FACE OF PORTS

# OUTLET VELOCITIES AND FLOW DISTRIBUTION TYPE 3 DESIGN, RIVERWARD WALL OUTLET STEADY-FLOW DISCHARGE RIVERWARD LOCK





PIEZOMETER LOCATIONS  
TYPES 2 AND 3 DISCHARGE OUTLETS  
TYPE 6 EMPTYING SYSTEM  
RIVERWARD LOCK







MINIMUM CULVERT ROOF PRESSURES  
 DOWNSTREAM OF EMPTYING SLIDE GATE  
 DURING NORMAL AND SINGLE  
 (RIGHT AND LEFT) GATE OPERATION  
 TYPE 6 SYSTEM  
 37.8-FT HEAD (UPPER POOL EL 725.0, LOWER POOL EL 687.2)  
 RIVERWARD LOCK





**NORMAL EMPTYING OPERATIONS**

SYMBOL	SLIDE GATE TIME, MIN	NO. BARGES	BOW STATION
—○—	2	80-80	0+05
—○—	4	2024	0+05
—○—	6	2030	3+05

NOTE: SLIDE GATE OPENING SCHEDULE  
CONSTANT SPEED  
BULKHEAD SLOTS DOWNSTREAM OF FILLING  
AND EMPTYING SLIDE GATES SEALED.





**SINGLE (RIGHT) SLIDE GATE OPERATIONS**



**SINGLE (LEFT) SLIDE GATE OPERATIONS**



**MAXIMUM HAWSER FORCES DURING  
NORMAL AND SINGLE SLIDE GATE  
EMPTYING OPERATION AT  
2, 4, 6, AND 8 MIN**  
TYPE 6 SYSTEM  
8.5-FT SUBMERGENCE, LOWER POOL EL 687.2  
37.8-FT HEAD






NOTE SLIDE GATE OPENING SCHEDULE  
CONSTANT SPEED, BULKHEAD SLOTS  
DOWNSTREAM OF EMPTYING SLIDE  
GATES SEALED.

**EMPTYING TIME VS  
SLIDE GATE OPENING TIME**  
NORMAL AND SINGLE (RIGHT AND LEFT)  
GATE OPERATIONS  
TYPE 6 SYSTEM  
38.5-FT HEAD, 8.5-FT SUBMERGENCE, LOWER POOL EL 6872  
RIVERWARD LOCK



SLIDE GATE OPENING SCHEDULE



HOIST LOADS  
TYPE 1 (ORIGINAL) SLIDE GATE  
NORMAL OPERATION, 4-MIN GATE SCHEDULE  
TYPE 5 FILLING SYSTEM








PLATE 58




HOIST LOADS  
TYPE I (ORIGINAL) SLIDE GATE  
NORMAL OPERATION, 4-MIN GATE SCHEDULE  
TYPE 6 EMPTYING SYSTEM




SLIDE GATE OPENING SCHEDULE




**HOIST LOADS**  
**TYPE 1 (ORIGINAL) SLIDE GATE**  
 SINGLE (RIGHT) 4-MIN GATE OPERATION  
 TYPE 6 EMPTYING SYSTEM





HOIST LOAD, KIPS



**SLIDE GATE OPENING SCHEDULE**




HOIST LOADS  
TYPE 1 (ORIGINAL) SLIDE GATE  
SINGLE (LEFT) 4-MIN GATE SCHEDULE  
TYPE 6 EMPTYING SYSTEM



SLIDE GATE OPENING SCHEDULE





In accordance with letter from DAEN-RDC, DAEN-ASI dated 22 July 1977, Subject: Facsimile Catalog Cards for Laboratory Technical Publications, a facsimile catalog card in Library of Congress MARC format is reproduced below.

Ables, Jackson H

Modifications to filling and emptying system of Lock No. 1, Mississippi River, Minneapolis, Minnesota; hydraulic model investigation / by Jackson H. Ables, Jr. Vicksburg, Miss. : U. S. Waterways Experiment Station ; Springfield, Va. : available from National Technical Information Service, 1979.

44, [31] p., [39] leaves of plates : ill. ; 27 cm.  
(Technical report - U. S. Army Engineer Waterways Experiment Station ; HL-79-21)

Prepared for U. S. Army Engineer District, St. Paul, St. Paul, Minnesota.

1. Hydraulic models. 2. Lock and Dam No. 1, Mississippi River. 3. Lock filling and emptying systems. 4. Locks (Waterways). 5. Mississippi River. I. United States. Army. Corps of Engineers. St. Paul District. II. Series: United States. Waterways Experiment Station, Vicksburg, Miss. Technical report ; HL-79-21.  
TA7.W34 no.HL-79-21